

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-065-03227-00-01
Spot: NWNWSENE Sec/Twnshp/Rge: 33-10S-23W
3658 feet from S Section Line, 1128 feet from E Section Line
Lease Name: DIEBOLT B Well #: 8W
County: GRAHAM Total Vertical Depth: 3778 feet

Operator License No.: 30606
Op Name: MURFIN DRILLING CO., INC.
Address: 250 N WATER STE 300
WICHITA, KS 67202

String	Size	Depth (ft)	Pulled (ft)	Comments
CIBP		3754		
PKR		3565		
PROD	5.5	3778		125 SX
SURF	8.625	220		175 SX
T1	2.375	3565		

Well Type: EOR UIC Docket No: E06808.4 Date/Time to Plug: 02/07/2013 12:00 PM
Plug Co. License No.: 30606 Plug Co. Name: MURFIN DRILLING CO., INC.
Proposal Rcvd. from: JOHN GERSTNER Company: MURFIN DRILLING CO., INC. Phone: (785) 421-2103

Proposed Plugging Method: Port Collar at 1870'. Cement unknown.
Squeezed at 1459' with 164 sx cement.
CIBP set at 3754'.
Perfs at 3616' to 3619' and 3743' to 3747'.
Ordered 300 sx 60/40 pozmix 4% gel cement, 11 sx gel and 600 # hulls.

Plugging Proposal Received By: MARVIN MILLS Witness Type: COMPLETE (100%)
Date/Time Plugging Completed: 02/07/2013 2:45 PM KCC Agent: MARVIN MILLS

Actual Plugging Report:

Ran tubing to 3600' and pumped 11 sx gel followed by 75 sx cement w/200 # hulls.
Pulled tubing to 1895' and pumped 220 sx cement. Good circulation of cement.
Pulled tubing. Topped off casing with 13 sx cement.
Tied on to back side and pumped 5 sx cement. Shut in pressure 500 psi.

Perfs:

Top	Bot	Thru	Comments
3757	3762		
3743	3747		
3616	3619		

Remarks: SWIFT CEMENT CO TICKET # 23810

Plugged through: TBG

District: 04

Signed [Signature]
(TECHNICIAN)

FEB 11 2013

RECEIVED

FEB 14 2013

KCC WICHITA

Form CP-2/3