

TO:  
STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING  
130 SOUTH MARKET, SUITE 2078  
WICHITA, KANSAS 67202

API Well Number: 15-007-10215-00-01  
Spot: SWSWNW Sec/Twnshp/Rge: 10-31S-15W  
2226 feet from N Section Line, 332 feet from W Section Line  
Lease Name: NATIONAL GYPSUM Well #: 1-A  
County: BARBER Total Vertical Depth: 4906 feet

Operator License No.: 33450  
Op Name: TERRA FIRMA EXPLORATION, INC.  
Address: 12601 JAYSON LN  
WICHITA, KS 67235

String	Size	Depth (ft)	Pulled (ft)	Comment
PROD	5.5	3543	2500	WITH 210 SX CMT
SURF	10.75	923		WITH 250 SX CMT

Well Type: GAS UIC Docket No: \_\_\_\_\_ Date/Time to Plug: 05/07/2013 1:30 PM  
Plug Co. License No.: 5105 Plug Co. Name: CLARKE CORPORATION  
Proposal Rcvd. from: MARK MORGENSTERN Company: CLARKE CORPORATION Phone: (620) 886-5665

Proposed Plugging Method: SAND TO 3140' WITH 5 SX CMT. PLUG AT 950' WITH 20 SX GEL & 75 SX CMT. PLUG AT 400' WITH 75 SX CMT. PLUG AT 60' WITH 30 SX CMT.

Plugging Proposal Received By: ERIC MACLAREN Witness Type: COMPLETE (100%)  
Date/Time Plugging Completed: 05/07/2013 3:00 PM KCC Agent: STEVE PFEIFER

Actual Plugging Report:

SANDED BACK TO 3120' & PUT 5 SX CMT ON TOP OF SAND BRIDGE THROUGH DUMP BAILER. 1ST PLUG AT 976' WITH 20 SX GEL & 75 SX CMT. 2ND PLUG AT 400' WITH 75 SX CMT. 3RD PLUG AT 60' WITH 30 SX CMT.

Perfs:

Top	Bot	Thru	Comments
3217	3223		
3192	3196		

Remarks: USED 60/40 POZMIX 4% GEL BY ALLIED.

Plugged through: TBG


RECEIVED  
KANSAS CORPORATION COMMISSION

MAY 13 2013

CONSERVATION DIVISION  
WICHITA, KS

District: 01

Signed

  
(TECHNICIAN)

RECEIVED

MAY - 9 2013

KCC DODGE CITY

AWJ