

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-135-25550-00-00
Spot: NWNWSENV Sec/Twnshp/Rge: 20-20S-22W
1365 feet from N Section Line, 1600 feet from W Section Line
Lease Name: WHITLEY Well #: 1
County: NESS Total Vertical Depth: 4420 feet

Operator License No.: 5259
Op Name: MAI OIL OPERATIONS, INC.
Address: 8411 PRESTON RD STE 800
DALLAS, TX 75225

String	Size	Depth (ft)	Pulled (ft)	Comment
SURF	8.625	262		WITH 165 SX CMT

Well Type: DH UIC Docket No: _____ Date/Time to Plug: 04/07/2013 2:00 AM
Plug Co. License No.: 33350 Plug Co. Name: SOUTHWIND DRILLING, INC.
Proposal Rcvd. from: BILL SANDERS Company: SOUTHWIND DRILLING, INC. Phone: (620) 564-3800

Proposed Plugging Method: 1ST PLUG AT 1430' WITH 50 SX CMT. 2ND PLUG AT 750' WITH 80 SX CMT. 3RD PLUG AT 400' WITH 30 SX CMT. 4TH PLUG AT 290' WITH 50 SX CMT. 5TH PLUG AT 60' WITH 20 SX CMT. 6TH PLUG TO CIRCULATE RAT HOLE WITH 30 SX CMT. 7TH PLUG TO CIRCULATE MOUSE HOLE WITH 20 SX CMT.

Plugging Proposal Received By: STEVE PFEIFER Witness Type: NONE
Date/Time Plugging Completed: 04/07/2013 4:30 AM KCC Agent: STEVE PFEIFER

Actual Plugging Report:

Perfs:

1ST PLUG AT 1430' WITH 50 SX CMT. 2ND PLUG AT 750' WITH 80 SX CMT. 3RD PLUG AT 400' WITH 30 SX CMT. 4TH PLUG AT 290' WITH 50 SX CMT. 5TH PLUG AT 60' WITH 20 SX CMT. 6TH PLUG TO CIRCULATE RAT HOLE WITH 30 SX CMT. 7TH PLUG TO CIRCULATE MOUSE HOLE WITH 20 SX CMT.

Remarks: USED 60/40 POZMIX 4% GEL 1/4# FLO SEAL BY ALLIED.

Plugged through: DP

RECEIVED
KANSAS CORPORATION COMMISSION

APR 15 2013

CONSERVATION DIVISION
WICHITA, KS

District: 01

Signed Stephen J Pfeifer
4/12/13 (TECHNICIAN)

RECEIVED
APR - 8 2013
KCC DODGE CITY