

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-113-20394-00-00
Spot: NESWNE Sec/Twnshp/Rge: 17-20S-1W
4450 feet from S Section Line, 948 feet from E Section Line
Lease Name: BULLINGER (LAWRENCE W) Well #: 1
County: MCPHERSON Total Vertical Depth: 3010 feet

Operator License No.: 5631
Op Name: LOEWEN OPERATOR, INC.
Address: 208 S MAIN PO BOX 335
CANTON, KS 67428

String	Size	Depth (ft)	Pulled (ft)	Comments
PROD	4.5	3010		100 SX
SURF	8.625	153		125 SX

Well Type: GAS UIC Docket No: _____ Date/Time to Plug: 02/11/2013 9:00 AM
Plug Co. License No.: 30280 Plug Co. Name: SUNFLOWER WELL SERVICE, INC.
Proposal Rcvd. from: ANDREW RHEA Company: _____ Phone: (620) 654-6976

Proposed Plugging Method: AS PER KCC RULES & REGS

Plugging Proposal Received By: HUNTER CLARK Witness Type: PARTIAL
Date/Time Plugging Completed: 02/12/2013 9:30 AM KCC Agent: HUNTER CLARK

Actual Plugging Report:

Perfs:


SAND BACK @ 2960' WITH A 4 SX CAP. TIED ON TO THE CASING PUMPED 250 SX OF 60/40 4% WITH NO CEMENT SHOW. RAN BAILER TAGGED CEMENT @ 1600'. GOT ANOTHER BULK TRUCK PUMPED 150 SX OF 60/40 4% WITH 200 LBS OF HULLS, STILL NO SHOW SHUT DOWN WAITED FOR CEMENT TO SET UP. 2/12/13 TAGGED CEMENT 220' DOWN 4.5" THEN RAN 1" DOWN THEN PUMPED 35 SX OF 60/40 4%. THEN RAN 250' OF 1" DOWN THE BACKSIDE AND PUMPED 100 SX OF 60/40 4% CEMENT CIRCULATED TO SURFACE.

Remarks: COPLAND TICKET #38240

Plugged through: TBG

District: 02

Signed


3/08/13 (TECHNICIAN)

RECEIVED
MAR 06 2013
KCC WICHITA