

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-051-26459-00-00
Spot: NENWNWSW Sec/Twnshp/Rge: 17-15S-19W
2500 feet from S Section Line, 550 feet from W Section Line
Lease Name: R.C. UNIT Well #: #1
County: ELLIS Total Vertical Depth: 3665 feet

Operator License No.: 33625

Op Name: HERTEL OIL COMPANY LLC

Address: 704 E 12TH ST
HAYS, KS 67601

String	Size	Depth (ft)	Pulled (ft)	Comments
SURF	8.625	1230		460 sx

Well Type: DH

UIC Docket No:

Date/Time to Plug: 01/21/2013 12:00 AM

Plug Co. License No.: 31548

Plug Co. Name: DISCOVERY DRILLING

Proposal Rcvd. from: TOM ALM

Company: DISCOVERY DRILLING

Phone: (785) 623-2920

Proposed Plugging Method: Ordered sx 60/40 pozmix - 4% gel cement with 1/4# flo- seal per sack.
Space all plugs with heavy drilling mud through drill pipe.

Plugging Proposal Received By: CASE MORRIS

WitnessType: NONE

Date/Time Plugging Completed: 01/21/2013 2:00 AM

KCC Agent: CASE MORRIS

Actual Plugging Report:

Perfs:

1st plug @1275 w/40 sx
2nd plug @500 w/80 sx
3rd plug @40 w/10 sx

Rathole 30 sx Mousehole 15 sx


Remarks: QUALITY

Plugged through: DP

RECEIVED
FEB 08 2013
KCC WICHITA

District: 04

Signed


2/20/13 (TECHNICIAN)

FEB 01 2013

Form CP-2/3