

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-147-20606-00-00
Spot: SWSESWSE Sec/Twnshp/Rge: 12-5S-20W
200 feet from S Section Line, 1850 feet from E Section Line
Lease Name: DEBRA UNIT Well #: 12-1
County: PHILLIPS Total Vertical Depth: 3744 feet

Operator License No.: 33335
Op Name: IA OPERATING, INC.
Address: 9915 W 21ST ST, STE B
WICHITA, KS 67205

String	Size	Depth (ft)	Pulled (ft)	Comments
PROD	5.2	3740	2009	165 SX
SURF	8.625	1689		675 SX
T1	2.375	3552		

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: 01/29/2013 9:00 AM
Plug Co. License No.: 32028 Plug Co. Name: CHITO'S WELL SERVICE, LLC
Proposal Rcvd. from: GEORGE YOUNGER Company: IA OPERATING INC. Phone: (785) 735-4966

Proposed Plugging Method: Ordered 325 sx 60/40 pozmix 4% gel cement w/500 # hulls.
Perforations: 3408'-3413', 3452'-3455', 3464'-3466', 3538'-3542'.
GPS: 39.62612N -099.52215
229' FSL 1845' FEL SW SE SW SE

Plugging Proposal Received By: PAT STAAB WitnessType: COMPLETE (100%)
Date/Time Plugging Completed: 01/29/2013 5:00 PM KCC Agent: PAT STAAB

Actual Plugging Report:

Sanded off bottom perms to 3200' and topped with 5 sx cement.
Nabors perforators shot casing off at 2009'. Chitos pulled casing to 1750'.
Quality rigged to casing and pumped 175 sx 60/40 pozmix w/300 # hulls mixed in.
Pulled casing to 1050' and pumped 50 sx 60/40 pozmix w/100 # hulls mixed in.
Pulled casing to 300' and pumped 60 sx 60/40 pozmix w/100 # hulls mixed in to circulate cement to surface. Pulled casing. Topped off hole with 20 sx. Hole standing full.

Perfs:

Top	Bot	Thru	Comments
3538	3542		
3464	3466		
3452	3455		
3408	3413		


RECEIVED
FEB 08 2013
KCC WICHITA

Remarks: QUALITY OILWELL CEMENTING TICKET # 6501

Plugged through: CSG

District: 04

Signed


2/20/13

(TECHNICIAN)

CM

JAN 30 2013