

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-193-20589-00-00
Spot: SWNWNWSW Sec/Twnshp/Rge: 28-8S-32W
2298 feet from S Section Line, 5046 feet from E Section Line
Lease Name: WEYAND Well #: 6
County: THOMAS Total Vertical Depth: 4700 feet

Operator License No.: 5285
Op Name: HANSEN, DANE G. - TRUST
Address: PO BOX 187
LOGAN, KS 67646

String	Size	Depth (ft)	Pulled (ft)	Comments
CIBP		2590		
PKR	5.5	2385		
PROD	5.5	2730		425 SX
SURF	8.625	364		200 SX
TI	2.375	2385		

Well Type: SWD UIC Docket No: D26536.0 Date/Time to Plug: 04/29/2013 11:00 AM
Plug Co. License No.: 33645 Plug Co. Name: H2 PLAINS, LLC
Proposal Rcvd. from: RONALD VANROEKEL Company: H2 PLAINS, LLC Phone: (785) 689-4816

Proposed Plugging Method: CIBP at 2590'. Perforations from 2435' - 2515'.
Ordered 350 sx 60/40 pozmix 4% gel cement and 500 # hulls.

Plugging Proposal Received By: DARREL DIPMAN Witness Type: COMPLETE (100%)
Date/Time Plugging Completed: 04/29/2013 2:15 PM KCC Agent: MARVIN MILLS

Actual Plugging Report:

Ran tubing to 2534' and pumped 125 sx cement w/300 # hulls.
Pulled tubing to 1330' and pumped 135 sx cement w/150 # hulls. Good circulation of cement.
Pulled tubing out. Topped of casing with 15 sx cement.
Tied on to back side. Braden head broke. Cannot pump cement in back side.
GPS: 39.32804 -100.90669

Perfs:

Top	Bot	Thru	Comments
2435	2515		

Remarks: CONSOLIDATED CEMENT CO TICKET # 39353

Plugged through: TBG

District: 04

Signed [Signature]
(TECHNICIAN)

CM

APR 30 2013

RECEIVED
KANSAS CORPORATION COMMISSION

MAY 06 2013

CONSERVATION DIVISION
WICHITA, KS