

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-163-21544-00-00
Spot: W2SWNW Sec/Twnshp/Rge: 18-9S-18W
1980 feet from N Section Line, 330 feet from W Section Line
Lease Name: BUTCHER Well #: 2
County: ROOKS Total Vertical Depth: 3650 feet

Operator License No.: 5453
Op Name: L-K WIRELINE, INC.
Address: PO BOX 1188
HAYS, KS 67601

| String | Size | Depth (ft) | Pulled (ft) | Comments |
|--------|-------|------------|-------------|----------|
| PROD | 5.5 | 3649 | 2322 | |
| SURF | 8.625 | 1455 | | |
| T1 | 2.875 | 3611 | | |

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: 05/01/2013 9:00 AM
Plug Co. License No.: 99977 Plug Co. Name: QUALITY OIL WELL CEMENTING
Proposal Rcvd. from: RANDY LONGPINE Company: LK WIRELINE Phone: (785) 623-1333

Proposed
Plugging
Method:

Ordered 300 sx 60/40 pozmix 4% gel cement w/500 # hulls.

Plugging Proposal Received By: CASE MORRIS WitnessType: PARTIAL
Date/Time Plugging Completed: 05/01/2013 1:30 PM KCC Agent: RICHARD WILLIAMS

Actual Plugging Report:

04/30/2013 - LK Wireline set 3 CIBP's at 3536', 3500' and 3250'.
Shot 5 1/2" casing off at 2322'. Shut Down-not witnessed.
05/01/2013 - Pulled 5 1/2" casing to 2002' and Quality Oilwell Cementing pumped 125 sx
cement w/200 # hulls. Circulated water.
Pulled casing to 1442' and pumped 50 sx cement w/100 # hulls. Circulated water.
Pulled casing to 882' and pumped 100 sx cement w/200 # hulls. Circulated water.
Pulled casing to 242' and pumped 40 sx cmenet. Circulated water and cement.
Pulled all casing, 8 5/8" casing full.

Perfs:

| Top | Bot | Thru | Comments |
|------|------|------|----------|
| 3541 | 3544 | | |
| 3535 | 3541 | | |
| 3528 | 3533 | | |
| 3524 | 3528 | | |
| 3520 | 3524 | | |
| 3516 | 3520 | | |

RECEIVED
KANSAS CORPORATION COMMISSION

Remarks: NOTHING WITNESED ON 04/30/2013. QUALITY OILWELL CEMENTING

MAY 06 2013

Plugged through: CSG

CONSERVATION DIVISION
WICHITA, KS

District: 04

Signed Richard Williams
5/13/13 (TECHNICIAN)

CM

MAY 02 2013