

TO:  
STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING  
130 SOUTH MARKET, SUITE 2078  
WICHITA, KANSAS 67202

API Well Number: 15-051-30083-00-02  
Spot: NESESESW Sec/Twnshp/Rge: 17-11S-18W  
349 feet from S Section Line, 2858 feet from E Section Line  
Lease Name: FRISBIE H Well #: 1  
County: ELLIS Total Vertical Depth: 3530 feet

Operator License No.: 9408  
Op Name: TRANS PACIFIC OIL CORPORATION  
Address: 100 S MAIN STE 200  
WICHITA, KS 67202

String	Size	Depth (ft)	Pulled (ft)	Comments
L1	4.5	3530	-3219	
PROD	5.5	3253		575 SX
SURF	8.625	1218		575 SX

Well Type: SWD UIC Docket No: D21458.0 Date/Time to Plug: 04/22/2013 11:00 AM  
Plug Co. License No.: 7023 Plug Co. Name: KLIMA WELL SERVICE, INC.  
Proposal Rcvd. from: KEN BUEHLER Company: TRANS PACIFIC OIL CORP. Phone: (785) 483-1821

Proposed Plugging Method: Ordered 625 sx 60/40 pozmix 4% gel cement w/800 # hulls.  
Alt I completion  
Perforations: 3501' - 3518'.  
GPS: 39.08940 -099.34374  
353' FSL 2986' FEL NW SE SE SW

Plugging Proposal Received By: PAT STAAB Witness Type: COMPLETE (100%)  
Date/Time Plugging Completed: 04/22/2013 4:10 PM KCC Agent: PAT STAAB

Actual Plugging Report:

Perf Tech perforated at 1175'.  
Klima Well Service ran in hole to 3300'. Quality rigged to tubing and pumped 165 sx cement w/300 # hulls mixed in.  
Pulled tubing to 1650' and pumped 150 sx w/400 # hulls to circulate cement to surface.  
Pulled tubing. Rigged to 5 1/2" casing and pumped 25 sx cement to pressure with 150 psi and 150 Psi shut in pressure.  
8 5/8" casing full of cement from squeeze and liner.

Perfs:

Remarks: QUALITY CEMENTING CO TICKET # 6656

Plugged through: TBG

RECEIVED  
KANSAS CORPORATION COMMISSION

MAY 03 2013

CONSERVATION DIVISION  
WICHITA, KS

District: 04

Signed [Signature] (TECHNICIAN)

CM

APR 24 2013