

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-097-20423-00-00
Spot: NENE Sec/Twnshp/Rge: 23-27S-17W
4719 feet from S Section Line, 610 feet from E Section Line
Lease Name: THOMPSON Well #: 1
County: KIOWA Total Vertical Depth: 4700 feet

Operator License No.: 5420
Op Name: WHITE & ELLIS DRILLING, INC.
Address: PO BOX 48848
WICHITA, KS 67201

String	Size	Depth (ft)	Pulled (ft)	Comment
CIBP		4050		WITH 2 SX CMT
CIBP		4120		
CIBP		4699		
PROD	4.5	4700	0	WITH 200 SX CMT
SURF	8.625	380		WITH 275 SX CMT

Well Type: GAS UIC Docket No: _____ Date/Time to Plug: 04/16/2013 10:45 AM
Plug Co. License No.: 6123 Plug Co. Name: CHASE WELL SERVICE, INC.
Proposal Rcvd. from: MIKE LINK Company: CHASE WELL SERVICE, INC. Phone: (620) 793-9556

Proposed Plugging Method: SET CIBP 50' ABOVE PERFS WITH 2 SX CMT. PERFORATE @ 1000' & CIRCULATE CMT TO SURFACE INSIDE 4 1/2" CASING & 4 1/2" X 8 5/8" ANNULUS.

Plugging Proposal Received By: MICHAEL MAIER WitnessType: COMPLETE (100%)
Date/Time Plugging Completed: 04/16/2013 11:15 AM KCC Agent: STEVE PFEIFER

Actual Plugging Report:

SET CIBP @ 4050' & PUT 2 SX CMT ON TOP OF CIBP THROUGH DUMP BAILER. PERFORATE @ 1000'. PUMP DOWN 4 1/2" CASING WITH 320 SX CMT. CMT CIRCULATED FILLING 4 1/2" CASING & 4 1/2" X 8 5/8" ANNULUS WITH CMT.

Perfs:

Top	Bot	Thru	Comments
4624	4634		

Remarks: USED 60/40 POZMIX 4% GEL BY COPELAND ACID & CEMENTING.

Plugged through: CSG

RECEIVED
KANSAS CORPORATION COMMISSION

APR 29 2013

CONSERVATION DIVISION
WICHITA, KS

District: 01

RECEIVED

APR 19 2013

KCC DODGE CITY

Signed

Stephen J. Jufin
5/14/13 (TECHNICIAN)

AWT