

TO:  
STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING  
130 SOUTH MARKET, SUITE 2078  
WICHITA, KANSAS 67202

API Well Number: 15-189-22019-00-01  
Spot: NESESW Sec/Twnshp/Rge: 3-32S-35W  
1250 feet from S Section Line, 2500 feet from W Section Line  
Lease Name: HELMLEY UNIT A Well #: 1-3  
County: STEVENS Total Vertical Depth: 2894 feet

Operator License No.: 5208  
Op Name: EXXONMOBIL OIL CORP  
Address: 14950 HEATHROW FORREST PKWY P  
HOUSTON, TX 77210

String	Size	Depth (ft)	Pulled (ft)	Comment
PROD	5.5	2883	0	WITH 125 SX CMT
SURF	8.625	624		WITH 325 SX CMT

Well Type: GAS UIC Docket No: \_\_\_\_\_ Date/Time to Plug: 03/14/2013 9:00 AM  
Plug Co. License No.: 33338 Plug Co. Name: ORR ENTERPRISES, INC.  
Proposal Rcvd. from: JOEL Company: ORR ENTERPRISES, INC. Phone: (580) 251-9618

Proposed Plugging Method: PLUGGING PROPOSAL SAME AS ACTUAL PLUGGING.

Plugging Proposal Received By: KEN JEHLIK WitnessType: NONE  
Date/Time Plugging Completed: 03/14/2013 3:00 PM KCC Agent: KEN JEHLIK

Actual Plugging Report:

PUMP 50 SX CMT W/100# HULLS AT 1638'. FILL UP AT 1638'. TAG TOC @ 1355'.  
PERFORATE SQUEEZE HOLES AT 674'. CIRCULATE CMT TO SURFACE USING 240  
SX CMT, LEAVING THE 5 1/2" CASING & 5 1/2" X 8 5/8" ANNULUS FULL OF CMT.

Perfs:

Top	Bot	Thru	Comments
2730	2750		
2684	2704		

RECEIVED  
KANSAS CORPORATION COMMISSION

MAR 29 2013

CONSERVATION DIVISION  
WICHITA, KS

Remarks: \*\*COMPLIANCE ISSUE: DENIED TA HIGH FL\*\* USED CLASS C CEMENT BY ORR ENTERPRISES.

Plugged through: CSG

District: 01

Signed

*[Handwritten Signature]*  
4/04/13

(TECHNICIAN)

RECEIVED

MAR 21 2013

KCC DODGE CITY

Form CP-2/3

*[Handwritten Initials]*