

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-067-20207-00-00
Spot: SESENWSW Sec/Twnshp/Rge: 30-27S-37W
1500 feet from S Section Line, 1250 feet from W Section Line
Lease Name: WILLIAMS 3 UNIT Well #: 4
County: GRANT Total Vertical Depth: 2875 feet

Operator License No.: 5208
Op Name: EXXONMOBIL OIL CORP
Address: 14950 HEATHROW FORREST PKWY P
HOUSTON, TX 77210

String	Size	Depth (ft)	Pulled (ft)	Comment
PROD	5.5	2875	0	WITH 375 SX CMT
SURF	8.625	645		WITH 400 SX CMT

Well Type: GAS UIC Docket No: _____ Date/Time to Plug: 03/20/2013 8:30 AM
Plug Co. License No.: 33338 Plug Co. Name: ORR ENTERPRISES, INC.
Proposal Rcvd. from: JOEL Company: ORR ENTERPRISES, INC. Phone: (580) 251-9618

Proposed Plugging Method: PLUGGING PROPOSAL SAME AS ACTUAL PLUGGING.

Plugging Proposal Received By: KEN JEHLIK Witness Type: NONE
Date/Time Plugging Completed: 03/20/2013 4:00 PM KCC Agent: KEN JEHLIK

Actual Plugging Report:

PUMP 30 SX CMT WITH HULLS TO 2630'. PLUG AT 1858' WITH 75 SX CMT WITH 100# HULLS. TAG TOC @ 1234'. RAN BOND LOG. TOC @ 910'. TEST CASING TO 500#. PERFORATE SQUEEZE HOLES AT 695'. TAKE INJECTION RATE. PUMP 245 SX CMT THRU SQUEEZE HOLES, LEAVING THE 8 5/8" X 5 1/2" ANNULUS & THE 5 1/2" CASING FULL OF CMT.

Perfs:

Top	Bot	Thru	Comments
2686	2822		OPEN PERFS

Remarks: USED CLASS C COMMON CEMENT BY ORR ENTERPRISES.

Plugged through: CSG


RECEIVED
KANSAS CORPORATION COMMISSION

MAR 29 2013

CONSERVATION DIVISION
WICHITA, KS

District: 01

Signed



(TECHNICIAN)

RECEIVED

MAR 26 2013

KCC DODGE CITY

AWY