

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-097-21682-00-01
Spot: E2NWNWSW Sec/Twnshp/Rge: 34-27S-18W
2310 feet from S Section Line, 455 feet from W Section Line
Lease Name: GENE EINSEL Well #: 1-34
County: KIOWA Total Vertical Depth: 4290 feet

Operator License No.: 3273
Op Name: HERMAN L. LOEB, LLC
Address: PO BOX 838
LAWRENCEVILLE, IL 62439

String	Size	Depth (ft)	Pulled (ft)	Comment
CIBP		4100		WITH 2 SX CMT
CIBP		4400		
PROD	4.5	4288	2165	WITH 375 SX CMT
SURF	8.625	322		WITH 275 SX CMT

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: 03/14/2013 9:00 AM
Plug Co. License No.: 99996 Plug Co. Name: ALLIED CEMENT COMPANY
Proposal Rcvd. from: SHANE PELTON Company: HERMAN L LOEB, LLC Phone: (719) 340-8987

Proposed Plugging Method: SET CIBP 50' ABOVE PERFS. PLUG AT 1200' WITH 15 SX GEL & 50 SX CMT. PLUG AT 330' WITH 50 SX CMT. PLUG AT 40' WITH 15 SX CMT.

Plugging Proposal Received By: MICHAEL MAIER WitnessType: NONE
Date/Time Plugging Completed: 03/14/2013 4:00 PM KCC Agent: MICHAEL MAIER

Actual Plugging Report:

SET CIBP @ 4100' WITH 2 SX CMT. 1ST PLUG AT 1199' WITH 15 SX GEL & 50 SX CMT. 2ND PLUG AT 358' WITH 50 SX CMT. 3RD PLUG AT 40' WITH 25 SX CMT.

Perfs:

Top	Bot	Thru	Comments
4416	4422		
4212	4220		

Remarks: USED 60/40 POZMIX 4% GEL BY ALLIED.

Plugged through: CSG

RECEIVED
KANSAS CORPORATION COMMISSION

MAR 29 2013

CONSERVATION DIVISION
WICHITA, KS

District: 01

RECEIVED
MAR 22 2013
KCC DODGE CITY

Signed Michael Maier
4/04/13 (TECHNICIAN)