

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-155-20779-00-00
Spot: SWNESE Sec/Twnshp/Rge: 18-25S-5W
2100 feet from S Section Line, 573 feet from E Section Line
Lease Name: MALONEY Well #: 1
County: RENO Total Vertical Depth: 3940 feet

Operator License No.: 3273
Op Name: HERMAN L. LOEB, LLC
Address: PO BOX 838
LAWRENCEVILLE, IL 62439

String	Size	Depth (ft)	Pulled (ft)	Comments
LI	4.5	3907		
PROD	5.5	3924		125 SX
SURF	8.625	234		175 SX

Well Type: SWD UIC Docket No: D20333.0 Date/Time to Plug: 02/14/2013 12:00 AM

Plug Co. License No.: 31529 Plug Co. Name: MIKE'S TESTING & SALVAGE, INC.

Proposal Rcvd. from: MIKE KELSO Company: MIKES TESTING Phone:

Proposed Plugging Method: AS PER KCC RULES & REGS

Plugging Proposal Received By: STEVE VANGIESON

Witness Type: PARTIAL

Date/Time Plugging Completed: 02/14/2013 4:00 PM

KCC Agent: B. J. HOPE

Actual Plugging Report:

Perfs:

2/13/13 SANDED BACK TO 3800' CAPPED WITH 4 SX CEMENT. (5.5" CASING HAD BEEN SQUEEZED AND 4.5" LINER RAN INTO 3907' AND CEMENT CIRCUALTED TO SURFACE, WITHIN LAST YEAR.) RAN TUBING INTO 775' SPOTTED 35 SX CEMENT, RAN TUBING INTO 260' BROUGHT TO SURFACE WITH 25 SX OF CEMENT. 2/14/13-- CUT BRADEN HEAD OFF, CEMENT HAD FELL BACK 1000' INSIDE 4.5", PUMPED ANOTHER 150 SX TO FILL 4.5 AND SURFACE. 2/15/13 CEMENT WAS AT TOP OF CASING WELDED METAL PLATE ON AND CLOSED.

RECEIVED
KANSAS CORPORATION COMMISSION

MAR 29 2013

CONSERVATION DIVISION
WICHITA, KS

Remarks: COPELAND CEMENTING OUT OF GREAT BEND, 60/40 4% POS MIX.

Plugged through: TBG

District: 02

Signed B. J. Hope
(TECHNICIAN)

cc to MIC 4/6/13
4/10/13