

TO:  
STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING  
130 SOUTH MARKET, SUITE 2078  
WICHITA, KANSAS 67202

API Well Number: 15-119-00134-00-00  
Spot: NWSESE Sec/Twnshp/Rge: 3-33S-29W  
990 feet from S Section Line, 990 feet from E Section Line  
Lease Name: BARRAGREE Well #: 1  
County: MEADE Total Vertical Depth: 5830 feet

Operator License No.: 32864  
Op Name: XTO ENERGY INC.  
Address: 210 PARK AVE STE 2350  
OKLAHOMA CITY, OK 73102

String	Size	Depth (ft)	Pulled (ft)	Comment
CIBP		5665		WITH 10 SX CMT
PROD	4.5	5829	1602	WITH 250 SX CMT
SURF	8.625	1552		WITH 675 SX CMT

Well Type: OG UIC Docket No: \_\_\_\_\_ Date/Time to Plug: 04/18/2013 11:00 AM  
Plug Co. License No.: 33338 Plug Co. Name: ORR ENTERPRISES, INC.  
Proposal Rcvd. from: RONNIE ORR Company: ORR ENTERPRISES, INC. Phone: (580) 251-9618

**Proposed Plugging Method:** Set CIBP @ +/- 5675' & cap w/ 10 sx cement. Cut 4 1/2" casing at freepoint (+/- 1600'), keeping hole full of 9 ppg, 36 vis mud at all times. Notify KCC of anticipated depth of cement plugs in accordance w/ covering known anhydrite formation. Pump additional cement if needed to cover zone. Pump +/- 50 sx of Class C cement 100' below - 100' above the cut off casing. Pump 75 sx of Class C cement from 1652' - 1452' (100' in/out of surface csg shoe). Tag plug & top off plug w/ additional cement if needed to bring TOC to 1452'. Pump 20 sx Class C cement from 64' - 4' below ground level. Weld on ID plate. Restore location to landowner specifications.

Plugging Proposal Received By: KEN JEHLIK Witness Type: NONE  
Date/Time Plugging Completed: 04/18/2013 2:00 PM KCC Agent: KEN JEHLIK

**Actual Plugging Report:**

CIBP @ 5665' WITH 10 SX CMT. 1ST PLUG AT 1702' WITH 125 SX CMT. 2ND PLUG AT 550' WITH 60 SX CMT. 3RD PLUG AT 64' WITH 20 SX CMT.

**Perfs:**

Top	Bot	Thru	Comments
5705	5706		

Remarks: USED COMMON CEMENT BY ORR ENTERPRISES.

Plugged through: TBG

RECEIVED  
KANSAS CORPORATION COMMISSION

APR 29 2013

CONSERVATION DIVISION  
WICHITA, KS

District: 01

Signed \_\_\_\_\_

RECEIVED

APR 23 2013

KCC DODGE CITY

(TECHNICIAN)