

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-175-00377-00-00
Spot: SESESENW Sec/Twnshp/Rge: 17-34S-34W
2397 feet from N Section Line, 2494 feet from W Section Line
Lease Name: HAMPTON E D Well #: 1-17
County: SEWARD Total Vertical Depth: 2770 feet

Operator License No.: 32864
Op Name: XTO ENERGY INC.
Address: 210 PARK AVE STE 2350
OKLAHOMA CITY, OK 73102

String	Size	Depth (ft)	Pulled (ft)	Comment
CIBP		2592		WITH 10 SX CMT
PROD	7	2760	0	WITH 800 SX CMT
SURF	10.75	695		WITH 250 SX CMT

Well Type: GAS UIC Docket No: _____ Date/Time to Plug: 04/16/2013 11:00 AM
Plug Co. License No.: 33338 Plug Co. Name: ORR ENTERPRISES, INC.
Proposal Rcvd. from: RONNIE ORR Company: ORR ENTERPRISES, INC. Phone: (580) 251-9618

Proposed Plugging Method: SET CIBP @ 2592' WITH 10 SX CMT. PLUG AT 1660' WITH 60 SX CMT. RUN BOND LOG TO VERIFY TOC. IF CMT IS ABOVE SURFACE CASING SHOE, RUN TBG TO 750' & SPOT 60 SX CMT. PERFORATE ABOVE TOC & CIRCULATE TO SURFACE. IF TOC IS BELOW SURFACE CASING SHOE, CUT & PULL CASING. RTIH TO 625' & SPOT 80 SX CMT, THEN 60' & CIRCULATE.

Plugging Proposal Received By: KEN JEHLIK Witness Type: PARTIAL
Date/Time Plugging Completed: 04/16/2013 2:30 PM KCC Agent: KENNY SULLIVAN

Actual Plugging Report:

SET CIBP @ 2592' WITH 10 SX CMT. LOADED HOLE WITH 100 BBL MUD. 1ST PLUG AT 1660' WITH 60 SX CMT. PRESSURE TESTED TO 500#. RAN CMT BONG LOG. TOC = 460'. RTIH TO 750' & PUMPED 50 SX CMT. PERFORATED AT 435' & PUMPED 260 SX CMT. CMT CIRCULATED.

Perfs:

Top	Bot	Thru	Comments
2750	2770		
2694	2739		
2666	2676		
2642	2652		

RECEIVED
KANSAS CORPORATION COMMISSION

MAY 01 2013

CONSERVATION DIVISION
WICHITA, KS

Remarks: USED COMMON CEMENT BY ORR ENTERPRISES.

Plugged through: TBG

District: 01

Signed _____

(TECHNICIAN)

RECEIVED

APR 23 2013

KCC DODGE CITY