

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-039-00594-00-00
Spot: SWNENWNW Sec/Twnshp/Rge: 4-4S-28W
510 feet from N Section Line, 810 feet from W Section Line
Lease Name: VAVROCH Well #: 8
County: DECATUR Total Vertical Depth: 3908 feet

Operator License No.: 34434
Op Name: EDISON OPERATING COMPANY LLC
Address: 8100 E. 22ND ST. N., BLDG 1900
WICHITA, KS 67226

String	Size	Depth (ft)	Pulled (ft)	Comments
PROD	4.5	3952		210 SX
SURF	8.625	250		220 SX

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: 04/16/2013 11:00 AM
Plug Co. License No.: 33755 Plug Co. Name: QUALITY PLUS OILFIELD SERVICES, LLC
Proposal Rcvd. from: ROCH MILLER Company: EDISON OPERATING CO LLC Phone: (620) 786-5161

Proposed Plugging Method: 8 5/8" surface casing set at 250' w/220 sx cement. 4 1/2" production casing set at 3952' w/210 sx cement. TD 3908', PBTD 3908'. Perforations: 3734' - 3740, 3756' - 3759', 3766' - 3768', 3773' - 3783', 3798' - 3802', 3813' - 3816', 3836' - 3842', 3869' - 3873' and 3892' - 3897'. Casing squeezes: 2138' w/300 sx cement, 2875' - 2955' w/150 sx cement and 2500' w/200 sx cement. 1600' of 2 7/8" tubing stuck in hole. Top of fish at 2160'.
Ordered 440 sx 60/40 pozmix 4% gel cement w/600 # hulls.

Plugging Proposal Received By: CASE MORRIS Witness Type: COMPLETE (100%)
Date/Time Plugging Completed: 04/16/2013 1:15 PM KCC Agent: DARREL DIPMAN

Actual Plugging Report:

Perforated production casing at 1780'.
Ran tubing to 2150' and pumped 175 sx cement w/200 # hulls. Cement to surface.
Pulled tubing to surface. Connected to 4 1/2" production casing and pumped 35 sx cement.
Casing full.
Connected to 8 5/8" surface casing. Pumped 5 sx cement. Cement circulated to surface from 4 1/2" production casing.
Cement in 8 5/8" surface casing to be checked when cut off. 4 1/2" capacity 137 sx and 8 5/8" surface casing 44 sx. Ordered extra cement due to poor casing condition.
Roustabout reported 8 5/8" surface casing full of cement.

Perfs:

Top	Bot	Thru	Comments
3892	3897		
3869	3873		
3836	3842		

Remarks: QUALITY

Plugged through: TBG

RECEIVED
KANSAS CORPORATION COMMISSION

MAY 06 2013

CONSERVATION DIVISION
WICHITA, KS

District: 04

Signed Darrel Dipman
(TECHNICIAN)

CM

APR 26 2013