

TO: STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING  
130 SOUTH MARKET, SUITE 2078  
WICHITA, KANSAS 67202

API Well Number: 15-047-20723-00-00  
Spot: NWSESENE Sec/Twnshp/Rge: 14-24S-17W  
3100 feet from S Section Line, 429 feet from E Section Line  
Lease Name: MALM Well #: 2-14  
County: EDWARDS Total Vertical Depth: 4455 feet

Operator License No.: 5056  
Op Name: F. G. HOLL COMPANY L.L.C.  
Address: 9431 E CENTRAL STE 100  
WICHITA, KS 67206

String	Size	Depth (ft)	Pulled (ft)	Comment
PROD	4.5	4450	2200	WITH 225 SX CMT
SURF	8.625	264		WITH 225 SX CMT

Well Type: OIL UIC Docket No: \_\_\_\_\_ Date/Time to Plug: 04/23/2013 12:30 PM  
Plug Co. License No.: 31925 Plug Co. Name: QUALITY WELL SERVICE, INC.  
Proposal Rcvd. from: RICHARD MCINTYRE Company: QUALITY WELL SERVICE, INC. Phone: (620) 727-3410

Proposed Plugging Method: SAND TO 4270' & 4 SX CMT. PLUG AT 1100' WITH 15 SX GEL & 50 SX CMT. PLUG AT 290' WITH 50 SX CMT. PLUG AT 40' WITH 20 SX CMT.

Plugging Proposal Received By: RICHARD LACEY WitnessType: NONE  
Date/Time Plugging Completed: 04/23/2013 2:00 PM KCC Agent: RICHARD LACEY

Actual Plugging Report:

SANDED TO 4230' & 4 SX CMT. 1ST PLUG AT 1110' WITH 12 SX GEL & 50 SX CMT.  
2ND PLUG AT 325' WITH 50 SX CMT. 3RD PLUG AT 34' WITH 20 SX CMT.

Perfs:

Top	Bot	Thru	Comments
4338	4327		

Remarks: USED 60/40 POZMIX 4% GEL BY QUALITY.

Plugged through: CSG

RECEIVED  
KANSAS CORPORATION COMMISSION

APR 29 2013

CONSERVATION DIVISION  
WICHITA, KS

District: 01

Signed

*Richard W. Lacy*  
5/13/13

(TECHNICIAN)

RECEIVED

APR 25 2013

KCC DODGE CITY

*Handwritten mark*