

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-047-21267-00-00
Spot: SWSENE Sec/Twnshp/Rge: 14-24S-17W
4057 feet from S Section Line, 429 feet from E Section Line
Lease Name: MALM Well #: 5-14
County: EDWARDS Total Vertical Depth: 4440 feet

Operator License No.: 5056
Op Name: F. G. HOLL COMPANY L.L.C.
Address: 9431 E CENTRAL STE 100
WICHITA, KS 67206

String	Size	Depth (ft)	Pulled (ft)	Comment
CIBP		4418		
PROD	4.5	4435	1880	WITH 225 SX CMT
SURF	8.625	307		WITH 225 SX CMT

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: 04/22/2013 10:00 AM
Plug Co. License No.: 31925 Plug Co. Name: QUALITY WELL SERVICE, INC.
Proposal Rcvd. from: RICHARD MCINTYRE Company: QUALITY WELL SERVICE, INC. Phone: (620) 727-3410

Proposed Plugging Method: SAND TO 4275' & 4 SX CMT. PLUG AT 1100' WITH 10 SX GEL & 50 SX CMT. PLUG AT 330' WITH 50 SX CMT. PLUG AT 40' WITH 20 SX CMT.

Plugging Proposal Received By: RICHARD LACEY Witness Type: COMPLETE (100%)
Date/Time Plugging Completed: 04/22/2013 2:55 PM KCC Agent: RICHARD LACEY

Actual Plugging Report:

SANDED TO 4270' & PLACED 4 SX CMT ON TOP OF SAND WITH DUMP BAILER.
1ST PLUG AT 1108' WITH 10 SX GEL & 50 SX CMT. 2ND PLUG AT 320' WITH 50 SX CMT. 3RD PLUG AT 39' WITH 20 SX CMT.

Perfs:

Top	Bot	Thru	Comments
4322	4336		

Remarks: USED 60/40 POZMIX 4% GEL BY QUALITY WELL SERVICE.

Plugged through: CSG

RECEIVED
KANSAS CORPORATION COMMISSION

APR 29 2013

CONSERVATION DIVISION
WICHITA, KS

District: 01

RECEIVED

APR 25 2013

KCC DODGE CITY

Signed

Richard M. Lacey
✓ 5/13/13

(TECHNICIAN)

AMS