

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-033-20872-00-01
Spot: NWSESENW Sec/Twnshp/Rge: 16-34S-20W
2300 feet from N Section Line, 2035 feet from W Section Line
Lease Name: SELZER Well #: 16-12
County: COMANCHE Total Vertical Depth: 6268 feet

Operator License No.: 3842
Op Name: LARSON ENGINEERING, INC. DBA LAR
Address: 562 W STATE RD 4
OLMITZ, KS 67564

| String | Size | Depth (ft) | Pulled (ft) | Comment |
|--------|-------|------------|-------------|-----------------|
| CIBP | | 4965 | | |
| CIBP | | 6050 | | |
| DVT | | 5517 | | |
| PROD | 5.5 | 6100 | 3225 | WITH 585 SX CMT |
| SURF | 8.625 | 673 | | WITH 320 SX CMT |

Well Type: OG UIC Docket No: _____ Date/Time to Plug: 02/19/2013 12:00 PM
Plug Co. License No.: 31925 Plug Co. Name: QUALITY WELL SERVICE, INC.
Proposal Rcvd. from: TOM LARSON Company: LARSON OPERATING Phone: (620) 653-7368

Proposed Plugging Method: PUMP 250# HULLS & 40 SX CMT ON BOTTOM. PLUG AT 830' WITH 15 SX GEL & 50 SX CMT. PLUG AT 720' WITH 50 SX CMT. PLUG AT 300' WITH 40 SX CMT. PLUG AT 40' WITH 20 SX CMT.

Plugging Proposal Received By: ERIC MACLAREN Witness Type: NONE
Date/Time Plugging Completed: 02/19/2013 2:00 PM KCC Agent: ERIC MACLAREN

Actual Plugging Report:

LOST GAMMA NEUTRON TOOL & FISHING TOOLS IN OPEN HOLE. TOP OF FISH @ 6076'. SET CIBP @ 6050' WITH 4 SX RED CMT. SET CIBP @ 4965' WITH 1 SX RED CMT. PUMPED 250# HULLS & 30 SX CMT ON BOTTOM. TOC @4640'. 1ST PLUG AT 830' WITH 15 SX GEL & 50 SX CMT. 2ND PLUG AT 710' WITH 40 SX CMT. 3RD PLUG AT 300' WITH 40 SX CMT. 4TH PLUG AT 42' WITH 20 SX CMT.

Perfs:

| Top | Bot | Thru | Comments |
|------|------|------|----------|
| 5940 | 6012 | | |
| 5036 | 5146 | | |
| 4848 | 4854 | | |
| 4296 | 4566 | | |

RECEIVED
KANSAS CORPORATION COMMISSION
MAR 27 2013
CONSERVATION DIVISION
WICHITA, KS

Remarks: USED 60/40 POZMIX 4% GEL BY QUALITY WELL SERVICE.

Plugged through: CSG

District: 01

RECEIVED
MAR 22 2013

KCC DODGE CITY

Signed [Signature]
4/08/13 (TECHNICIAN)

AMY