

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-159-01771-00-00
Spot: SENWNW Sec/Twnshp/Rge: 31-18S-7W
4268 feet from S Section Line, 4293 feet from E Section Line
Lease Name: J POWELL Well #: 6
County: RICE Total Vertical Depth: 3245 feet

Operator License No.: 30425
Op Name: DNR OIL AND GAS, INC.
Address: 12741 E CALEY UNIT 142
CENTENNIAL, CO 80111

String	Size	Depth (ft)	Pulled (ft)	Comments
PROD	5	3244		175 SX
SURF	8	325		225 SX

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: 01/22/2013 11:00 AM
Plug Co. License No.: 31529 Plug Co. Name: MIKE'S TESTING & SALVAGE, INC.
Proposal Rcvd. from: MIKE KELSO Company: MIKES TESTING & SALVAGE, INC. Phone: (620) 562-8088

Proposed Plugging Method: To be plugged per KCC rules and regulations

Plugging Proposal Received By: PATRICK SHIELDS Witness Type: PARTIAL
Date/Time Plugging Completed: 01/22/2013 2:00 PM KCC Agent: VIRGIL CLOTHIER

Actual Plugging Report:

MIRU, CK BOTTOM. SAND PERFS TO 3120' AND CAP WITH 5 SX'S CEMENT. PERFOATE AT 1050', 700', AND 375'. RUN TUBING TO 1050' AND PUMP 35 SX'S COMMON CEMENT. PULL TUBING UP TO 700', LET SET FOR 1 HOUR -- ATTEMPTED TO TAG -- COULD NOT TAG. RUN TUBING BACK DOWN TO 1050' -- STARTED PUMPING, HAD GOOD CIRCULATION -- CIRCULATED CEMENT TO SURFACE. SHUT VALVE ON CASING -- PUMPED CEMENT -- PRESSURED UP TO 250#S. NEVER DID GET CEMENT OUT OF SURFACE CASING -- CONNECTED ONTO SURFACE CASING -- PUMPED 5 SX'S -- PRESSURED UP TO 300#S. PULL TUBING OUT AND TOP OFF.

Perfs:

Top	Bot	Thru	Comments
3175	3203	CSG	

RECEIVED
FEB 18 2013
KCC WICHITA

Remarks: LOG TECH OF KS. #7347. COPELAND TICKET #C-38229/ OVER 10 YEARS INACTIVE

Plugged through: TBG

District: 02

Signed

Virgil Clothier
2/20/13
(TECHNICIAN)

JK