

TO: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-159-01772-00-00
Spot: NWNWNW Sec/Twnshp/Rge: 31-18S-7W
4932 feet from S Section Line, 4955 feet from E Section Line
Lease Name: J POWELL Well #: 7
County: RICE Total Vertical Depth: 3216 feet

Operator License No.: 30425
Op Name: DNR OIL AND GAS, INC.
Address: 12741 E CALEY UNIT 142
CENTENNIAL, CO 80111

String	Size	Depth (ft)	Pulled (ft)	Comments
PROD	5	3215		170 SX
SURF	8	280		220 SX

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: 01/23/2013 10:00 AM
Plug Co. License No.: 31529 Plug Co. Name: MIKE'S TESTING & SALVAGE, INC.
Proposal Rcvd. from: JAMIE HARRIS Company: MIKE'S TESTING & SALVAGE, INC. Phone: (620) 562-8088

Proposed Plugging Method: To be plugged per KCC rules and regulations.

Plugging Proposal Received By: VIRGIL CLOTHIER Witness Type: PARTIAL
Date/Time Plugging Completed: 01/23/2013 1:00 PM KCC Agent: VIRGIL CLOTHIER

Actual Plugging Report:

MIRU, CK BOTTOM. SAND PERFS TO 3110' AND CAP WITH 5 SX'S CEMENT. PERFORATE AT 1050', 700', AND 330'. RUN TUBING TO 1050' AND PUMP CEMENT TO SURFACE -- PRESSURED UP TO 200#'S. SHUT VALVE ON CASING AND CIRCULATED CEMENT ON BACKSIDE. PULL TUBING OUT AND TOP OFF.

Perfs:

Top	Bot	Thru	Comments
3169	3193	CSG	

RECEIVED
FEB 18 2013
KCC WICHITA

Remarks: COPELAND C-41774. LOG TECH OF KS #7349. OVER 10 YEARS INACTIVE

Plugged through: TBG

District: 02

Signed Virgil Clothier
2/20/13 (TECHNICIAN)

✓ JK