

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-189-22661-00-00
Spot: SWSWSW Sec/Twnshp/Rge: 33-33S-38W
330 feet from S Section Line, 330 feet from W Section Line
Lease Name: MORGAN TRUST Well #: 33 #1
County: STEVENS Total Vertical Depth: 6750 feet

Operator License No.: 5278
Op Name: EOG RESOURCES, INC.
Address: 3817 NW EXPRESSWAY STE 500
OKLAHOMA CITY, OK 73112

String	Size	Depth (ft)	Pulled (ft)	Comment
CIBP		6144		WITH 5 SX CMT
PROD	4.5	6748	2884	WITH 205 SX CMT
SURF	8.625	1658		WITH 480 SX CMT

Well Type: GAS UIC Docket No: _____ Date/Time to Plug: 02/03/2013 1:00 PM

Plug Co. License No.: 33338 Plug Co. Name: ORR ENTERPRISES, INC.

Proposal Rcvd. from: FRED KRESS Company: _____ Phone: _____

Proposed Plugging Method: Set CIBP @ 6144' w/ 5 sks cement . Circulate casing w/ mud . Cut & pull 4 1/2" casing from free point . Run tbg @ 1688' & spot 80 sks Class "C" cement up to 1393'. Pull up hole w/ tbg @ 730' & spot 60 sks cement up to 509'. Top out 64' - 4' w/ 20 sks cement.

Plugging Proposal Received By: KEN JEHLIK

WitnessType: NONE

Date/Time Plugging Completed: 02/04/2013 3:00 PM

KCC Agent: KEN JEHLIK

Actual Plugging Report:

CIBP @ 6144' WITH 5 SX CMT. 1ST PLUG AT 1688' WITH 80 SX CMT. 2ND PLUG AT 730' WITH 60 SX CMT. 3RD PLUG AT 64' WITH 20 SX CMT.

Perfs:


Top	Bot	Thru	Comments
6194	6212		

RECEIVED
FEB 08 2013
KCC WICHITA

Remarks: USED CLASS C COMMON CEMENT BY ORR ENTERPRISES.

Plugged through: TBG

District: 01

Signed 
(TECHNICIAN)

RECEIVED
FEB - 5 2013
KCC DODGE CITY

AWY