

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-163-20931-00-00
Spot: SWSWNW Sec/Twnshp/Rge: 31-10S-16W
2970 feet from S Section Line, 4950 feet from E Section Line
Lease Name: WHISMAN Well #: A-1
County: ROOKS Total Vertical Depth: 3565 feet

Operator License No.: 5042
Op Name: EDMISTON OIL COMPANY, INC.
Address: 125 N MARKET STE 1130
WICHITA, KS 67202

String	Size	Depth (ft)	Pulled (ft)	Comments
PROD	4.5	3558		125 SX
SURF	8.625	210		125 SX

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: 02/12/2013 12:30 PM
Plug Co. License No.: 6901 Plug Co. Name: D S & W WELL SERVICING, INC.
Proposal Rcvd. from: SHANNON RAYBERN Company: EDMISTON OIL CO., INC. Phone: (620) 793-2672

Proposed Plugging Method: Ordered 350 sx 60/40 pozmix 4% gel cement w/500 # hulls.
Perforations at 3402' - 3410'; 3306' - 3311'; 3280' - 3410'.
Milled on well two full days. Got to 1985'. Was losing hole. Bad Casing.

GPS: 39.14131N -099.15747W
2980' FSL 4717' FEL NE SW SW NW

Plugging Proposal Received By: PAT STAAB WitnessType: COMPLETE (100%)
Date/Time Plugging Completed: 02/12/2013 3:45 PM KCC Agent: PAT STAAB

Actual Plugging Report:

DS&W ran in hole with tubing to 1985'. Consolidated rigged to tubing and pumped 75 sx neat cement.
Pulled tubing to 1000'. Consolidated rigged to tubing and pumped 90 sx w/200 # hulls mixed in to circulate cement up 4 1/2" casing.
Pulled tubing. Rigged to 4 1/2" casing with a swedge and pumped 105 sx cement to circulate cement up 8 5/8" casing. Shut in 8 5/8" and 4 1/2" casing. Pressured to 200 psi. Shut in pressure 100 psi.

Perfs:


Top	Bot	Thru	Comments
3402	3410		
3306	3311		
3280	3410		

Remarks: CONSOLIDATED CEMENTING CO TICKET # 39333

Plugged through: TBG

District: 04

Signed


7/28/13 (TECHNICIAN)

FEB 16 2013

RECEIVED
FEB 22 2013

Form CP-2/3

KCC WICHITA