

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-109-20246-00-00
Spot: W2E2NENW Sec/Twnshp/Rge: 17-12S-33W
660 feet from N Section Line, 1990 feet from W Section Line
Lease Name: JANICE Well #: 1
County: LOGAN Total Vertical Depth: 4820 feet

Operator License No.: 34318
Op Name: BEREXCO LLC
Address: 2020 N. BRAMBLEWOOD
WICHITA, KS 67206

String	Size	Depth (ft)	Pulled (ft)	Comments
PROD	4.5	4818		250 SX
SURF	8.625	353		250 SX

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: 01/17/2013 10:30 AM
Plug Co. License No.: 3152 Plug Co. Name: POE SERVICING INC
Proposal Rcvd. from: MARK LEIKER Company: BEREN CORPORATION Phone: (316) 772-8649

Proposed Plugging Method: Ordered 450 sx 60/40 pozmix 4% gel cement w/650 # hulls.
8 5/8" surface casing set at 353' w/250 sx cement. 4 1/2" production casing set at 4818' w/250 sx cement.
TD 4820'. PBD 4771'. Perforations: 4044' - 4050', 4258' - 4261' and 4618' - 4628'. CIBP at 4600'

Plugging Proposal Received By: CASE MORRIS Witness Type: COMPLETE (100%)
Date/Time Plugging Completed: 01/17/2013 3:05 PM KCC Agent: DARREL DIPMAN

Actual Plugging Report:

Perfs:

Perforated production casing at 2622' and 1634'.
Ran tubing to 4580' and pumped 125 sx cement w/250 # hulls.
Pulled tubing to 2650' and pumped 100 sx cement w/200 # hulls.
Pulled tubing to 1325' and pumped 100 sx cement w/200 # hulls. Cement to surface.
Pulled tubing to surface. Connected to 4 1/2" casing and pumped 15 sx cement.
Connected to 8 5/8" surface casing and pumped 65 sx cement.

GPS: 39.01583 N -101.01088 W

RECEIVED
KANSAS CORPORATION COMMISSION

MAY 06 2013

CONSERVATION DIVISION
WICHITA, KS

Remarks: POE SERVICING. CONSOLIDATED CEMENT TICKET # 39,237

Plugged through: TBG

District: 04

Signed Darrel Dipman
5/10/13 (TECHNICIAN)

CM