

TO: STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING  
130 SOUTH MARKET, SUITE 2078  
WICHITA, KANSAS 67202

API Well Number: 15-163-02982-00-01  
Spot: SENENW Sec/Twnshp/Rge: 5-8S-17W  
4290 feet from S Section Line, 2970 feet from E Section Line  
Lease Name: ECKERT 'A' Well #: 1  
County: ROOKS Total Vertical Depth: 550 feet

Operator License No.: 31171  
Op Name: CONTINENTAL OPERATING CO.  
Address: 1221 MCKINNEY STE 3700  
HOUSTON, TX 77010

String	Size	Depth (ft)	Pulled (ft)	Comments
PROD	0	0		0 SX
SURF	8.625	131		60 SX

Well Type: WSW UIC Docket No: \_\_\_\_\_ Date/Time to Plug: 03/20/2013 11:30 AM  
Plug Co. License No.: 34115 Plug Co. Name: SCHIPPERS OILFIELD SERVICES, LLC  
Proposal Rcvd. from: RALPH BRUNGARDT Company: SCHIPPERS OILFIELD SERVICES, L Phone: (785) 735-4645

Proposed Plugging Method: Ordered 275 sx 60/40 pozmix 4% gel cement.  
Got to 1500' while drilling out hole went out at casing. Spotted 100 sx cement at 1500'. Tried to drill back out but went out of casing at 550' and well started flowing.  
GPS: 38.79413 -099.33595

Plugging Proposal Received By: CASE MORRIS Witness Type: COMPLETE (100%)  
Date/Time Plugging Completed: 03/20/2013 11:30 AM KCC Agent: TOM CULLEY

Actual Plugging Report:

Ran tubing to 400' and stacked out. Tried to circulate hole clean to 550'. Could not get tubing down. Circulated from 400' w/275 sx cement. POOH. Pressured casing to 250 psi. Backside full.

Perfs:

Remarks: SOS TICKET # 679

Plugged through: TBG

RECEIVED  
KANSAS CORPORATION COMMISSION

APR 02 2013

CONSERVATION DIVISION  
WICHITA, KS

District: 04

Signed \_\_\_\_\_

*Tom Culley*  
4/10/13 (TECHNICIAN)

CM

MAR 27 2013

Form CP-2/3