

TO:  
STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING  
130 SOUTH MARKET, SUITE 2078  
WICHITA, KANSAS 67202

API Well Number: 15-035-19144-00-00  
Spot: SWSWNESE Sec/Twnshp/Rge: 33-31S-4E  
1642 feet from S Section Line, 1079 feet from E Section Line  
Lease Name: BERNSTORF Well #: 2  
County: COWLEY Total Vertical Depth: 2120 feet

Operator License No.: 30169  
Op Name: DOUBLE "D" OIL COMPANY, INC.  
Address: 2009 JEAN CT  
WINFIELD, KS 67156

String	Size	Depth (ft)	Pulled (ft)	Comments
PROD	5.5	2004		100 SX
SURF	8.625	210		50 SX

Well Type: SWD UIC Docket No: D07323.0 Date/Time to Plug: 01/09/2013 8:00 AM  
Plug Co. License No.: 5495 Plug Co. Name: MCPHERSON, BILL AND/OR PENNY M. DBA MCPHERSON DRILLING  
Proposal Rcvd. from: DONALD L BUTLER Company: Phone: (620) 222-2500

Proposed Plugging Method: AS PER KCC RULES & REGS

Plugging Proposal Received By: DUANE KRUEGER Witness Type: PARTIAL  
Date/Time Plugging Completed: 01/09/2013 5:00 PM KCC Agent: DUANE KRUEGER

Actual Plugging Report:

SANDED WELL BACK @ 1900', RIH W/TBG @ 1800', MCPHERSON DRILLING ESTABLISHED CIRCULATION, & PUMPED 50 SXS CLASS A COMMON CEMENT & DISPLACED IN CASING. TAGGED CEMENT @ 1195'. RIH ON WIRELINE SHOT SQUEEZE HOLES @ 275' - 276' (2 HOLES). SWEDGED IN TO 5-12" CASING. WELL WOULD NOT CIRCULATE. RIH W/1" STEEL BETWEEN 8-5/8" & 5-1/2" @ 50', & RIH W/ 2-3/8" TBG INSIDE 5-1/2" CASING @ 280'. MCPHERSON DRILLING PUMPED 110 SXS CLASS A COMMON CEMENT TO SURFACE ON BOTH STRINGS. CEMENT CIRCULATED. 1-15-2013, TAGGED CEMENT @ 32', TOPPED CEMENT BACK TO SURFACE W/ 5 SXS. DANIELS READY MIX TICKET #27503 BOTTOM PLUG, & 27550 TOP PLUG.

Perfs:

Top	Bot	Thru	Comments
2004	2120	OH	

RECEIVED  
KANSAS CORPORATION COMMISSION  
MAR 29 2013

Remarks: FAILED MIT

Plugged through: TBG

District: 02

Signed Duane Krueger  
(TECHNICIAN)

cc to UIC 4/02/13  
4/18/13

CONSERVATION DIVISION  
WICHITA, KS