

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-163-20713-00-00
Spot: N2NE Sec/Twnshp/Rge: 35-8S-18W
660 feet from N Section Line, 1320 feet from E Section Line
Lease Name: DECHANT Well #: 3
County: ROOKS Total Vertical Depth: 3474 feet

Operator License No.: 5552
Op Name: GORE OIL COMPANY
Address: 202 S ST FRANCIS PO BOX 2757
WICHITA, KS 67202

String	Size	Depth (ft)	Pulled (ft)	Comments
PROD	4.5	3473		150 SX
SURF	8.625	169		125 SX

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: 03/20/2013 10:00 AM
Plug Co. License No.: 30606 Plug Co. Name: MURFIN DRILLING CO., INC.
Proposal Rcvd. from: LENNY DINKEL Company: GORE OIL CO Phone: (785) 259-1928

Proposed Plugging Method: Ordered 400 sx 60/40 pozmix 4% gel cement w/500 # hulls.
Squeeze jobs at 675' - 881' w/175 sx cement; 685' - 716', 848' - 881' w/150 sx cement; 810' w/150 sx cement; 2864' w/100 sx cement.
Perforations: 3194' - 3414' LKC
GPS: 39.31941 -099.29304
4605' FSL 1331' FEL NE SE NW NE

Plugging Proposal Received By: RICHARD WILLIAMS WitnessType: COMPLETE (100%)
Date/Time Plugging Completed: 03/20/2013 1:15 PM KCC Agent: PAT STAAB

Actual Plugging Report:

Murfin ran in hole with tubing to 2976' and pumped 100 sx cement w/150 # hulls.
Pulled tubing to 1984' and pumped 100 sx cement w/250 # hulls.
Pulled tubing to 992' and pumped 75 sx cement w/100 # hulls.
Pulled tubing. Rigged to 4 1/2" casing and pumped 85 sx cement to pressure with 200 psi.
Well had slow bleed off on shut in pressure.
Rigged to 8 5/8" casing and pumped 40 sx cement w/200 psi and 200 psi shut in pressure.
Operator ordered an additional 200 sx common cement and pumped 40 sx cement.
Pressured up 4 1/2" casing with 350 psi and 300 shut in pressure at 4:25pm.

Perfs:

Top	Bot	Thru	Comments
3410	3414		
3389	3391		
3369	3371		
3360	3364		
3348	3350		
3322	3325		
3290	3294		
3280	3284		
3231	3237		
3194	3196		

RECEIVED
KANSAS CORPORATION COMMISSION

APR 05 2013


CONSERVATION DIVISION
WICHITA, KS

Remarks: SWIFT SERVICES TICKET # 24026

Plugged through: TBG

District: 04

Signed


4/17/13 (TECHNICIAN)

CM

MAR 21 2013