

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-063-21938-00-00
Spot: SWSESWNE Sec/Twnshp/Rge: 33-13S-31W
2581 feet from N Section Line, 1797 feet from E Section Line
Lease Name: KLAUS-CAMPBELL Well #: 1-33
County: GOVE Total Vertical Depth: 4700 feet

Operator License No.: 9855
Op Name: GRAND MESA OPERATING COMPANY
Address: 1700 N WATERFRONT PKWY BLDG 600
WICHITA, KS 67206

String	Size	Depth (ft)	Pulled (ft)	Comments
PROD	5.5	4694		175 SX
SURF	8.625	220		165 SX
T1	2.875	4637		

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: 03/21/2013 2:30 PM
Plug Co. License No.: 32382 Plug Co. Name: SWIFT SERVICES, INC.
Proposal Rcvd. from: JOHN JOHNSON Company: GRAND MESA OPERATING CO. Phone: (316) 265-3000

Proposed Plugging Method: Top down plug. Ordered 400 sx 60/40 pozmix 4% gel cement, 12/100 # sx gel and 300 # hulls. 8 5/8" surface casing set at 220' w/165 sx cement. 5 1/2" production casing set at 4694' w/175 sx cement. Stage collar at 2405' w/255 sx cement. TD 4700'. PBTD 4683'. Perforations at 4530' - 4534' and 4539' - 4546'.

Plugging Proposal Received By: CASE MORRIS Witness Type: COMPLETE (100%)
Date/Time Plugging Completed: 03/21/2013 4:00 PM KCC Agent: DARREL DIPMAN

Actual Plugging Report:

Connected to 5 1/2" production casing. Pumped 60 sx cement mixed with 300 # hulls, 12/100 # sx gel and 240 sx cement. Max pressure 850 psi.
Connected to 8 5/8" surface casing. Pumped 10 sx cement. Maximum pressure 500 psi.
Plug complete.

GPS: 38.88099N -100.76729W

Perfs:

Top	Bot	Thru	Comments
4539	4546		
4530	4534		

Remarks: SWIFT SERVICES TICKET # 24,241

Plugged through: CSG

RECEIVED
KANSAS CORPORATION COMMISSION

APR 05 2013

CONSERVATION DIVISION
WICHITA, KS

District: 04

Signed Darrel Dipman
4/17/13 (TECHNICIAN)

CM

MAR 22 2013