

TO:  
STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING  
130 SOUTH MARKET, SUITE 2078  
WICHITA, KANSAS 67202

API Well Number: 15-009-16562-00-00  
Spot: SESE Sec/Twnshp/Rge: 8-20S-15W  
660 feet from S Section Line, 660 feet from E Section Line  
Lease Name: ADOLPH (STORAGE) Well #: 2  
County: BARTON Total Vertical Depth: 3800 feet

Operator License No.: 5399  
Op Name: TREK AEC, LLC  
Address: 155 N MARKET STE 710  
WICHITA, KS 67202

String	Size	Depth (ft)	Pulled (ft)	Comments
COND	0	0		0 SX
PROD	5	3800	2000	0 SX
SURF	8	1015		0 SX

Well Type: GAS UIC Docket No: \_\_\_\_\_ Date/Time to Plug: 04/11/2013 9:00 AM  
Plug Co. License No.: 31528 Plug Co. Name: MIKE KELSO OIL, INC.  
Proposal Rcvd. from: THAD STARR Company: TREK AEC, LLC Phone: (620) 793-2146

Proposed Plugging Method: Ordered 350 sx 60/40 pozmix 4% gel cement w/500 # hulls.  
Well is old gas storage site.

Plugging Proposal Received By: BRUCE RODIE Witness Type: COMPLETE (100%)  
Date/Time Plugging Completed: 04/11/2013 5:00 PM KCC Agent: BRUCE RODIE

Actual Plugging Report:

Set plug above perforations and topped with 2 sx cement.  
Cut casing at 2000'. Pulled casing to 1650', tied to casing and pumped 150 sx cement.  
Pulled casing to 1100', tied to casing and pumped 50 sx cement w/100 # hulls.  
Pulled casing to 650' and circulated cement to surface with 150 sx cement and 100 # hulls.  
GPS: 38.32110 -098.99440

Perfs:

Top	Bot	Thru	Comments
3763	3777		

Remarks: COPELAND ACID AND CEMENTING

Plugged through: CSG

RECEIVED  
KANSAS CORPORATION COMMISSION

MAY 03 2013

CONSERVATION DIVISION  
WICHITA, KS

District: 04

Signed Bruce Rodie  
6/11/13 (TECHNICIAN)

CM

APR 18 2013