

TO: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-015-19606-00-00
Spot: SESWNW Sec/Twnshp/Rge: 9-25S-5E
2956 feet from S Section Line, 4341 feet from E Section Line
Lease Name: WILSON A Well #: 133
County: BUTLER Total Vertical Depth: 2417 feet

Operator License No.: 5030
Op Name: VESS OIL CORPORATION
Address: 1700 WATERFRONT PKWY BLDG 500
WICHITA, KS 67206

String	Size	Depth (ft)	Pulled (ft)	Comments
PROD	6.625	2401		0 SX
SURF	8.25	2115		0 SX

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: 04/03/2013 8:00 AM
Plug Co. License No.: 32991 Plug Co. Name: SIMMONS WELL SERVICE, INC.
Proposal Rcvd. from: CASEY COATS Company: VESS OIL CORPORATION Phone: (316) 655-1997

Proposed Plugging Method: AS PER KCC RULES & REGS

Plugging Proposal Received By: DUANE KRUEGER Witness Type: COMPLETE (100%)
Date/Time Plugging Completed: 04/03/2013 5:00 PM KCC Agent: DUANE KRUEGER

Actual Plugging Report:

RIH W/TBG @ 2400', CONSOLIDATED OIL WELL SERVICES MIXED & PUMPED 75 SXS CLASS A COMMON, 3.5% CC & DISPLACED IN CSG. WAITED 2 HOURS ON CEMENT. TAGGED CEMENT @ 1997'. RIH W/TBG @ 750', CONSOLIDATED OIL WELL SERVICES MIXED & PUMPED 125 SXS CLASS A COMMON, 3.5% CC & DISPLACED IN CASING. PULLED TBG @ 300', REVERSED CIRCULATED TO SURFACE. (CIRCULATED CEMENT BACK). WAITED 2 HOURS, RIH ON WIRELINE TAGGED CEMENT @ 306', SHOT SQUEEZE HOLES 304'-305' (4 SHOTS). SWEDGED INTO CASING, CONSOLIDATED OIL WELL SERVICES MIXED & PUMPED 100 SXS CLASS A COMMON 3.5 % CC. CEMENT CIRCULATED. SHUT IN UNDER PRESSURE (800#). PLUG DOWN 5:00 PM, 4-3-2013, CONSOLIDATED CEMENT TICKET # 38534.

Perfs:

Top	Bot	Thru	Comments
2401	2417	OH	

RECEIVED
KANSAS CORPORATION COMMISSION
APR 17 2013
CONSERVATION DIVISION
WICHITA, KS

Remarks:

Plugged through: TBG

District: 02

Signed

DUANE KRUEGER
4/16/13 (TECHNICIAN)