

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-119-21327-00-00
Spot: SWNE Sec/Twnshp/Rge: 17-33S-29W
1980 feet from N Section Line, 1980 feet from E Section Line
Lease Name: UTZ Well #: 2-17
County: MEADE Total Vertical Depth: 6210 feet

Operator License No.: 32211
Op Name: O'BRIEN ENERGY RESOURCES CORP.
Address: 18 CONGRESS ST, STE 207
PORTSMOUTH, NH 03801

String	Size	Depth (ft)	Pulled (ft)	Comment
L1	2.875	6200	4484	
PROD	4.5	6114	4930	WITH 300 SX CMT
SURF	8.625	1492		WITH 550 SX CMT

Well Type: OG UIC Docket No: _____ Date/Time to Plug: 01/25/2013 12:00 PM
Plug Co. License No.: 34069 Plug Co. Name: BASIC ENERGY SERVICES, LP
Proposal Rcvd. from: ROGER PEARSON Company: PEARSON CONSULTING Phone: (620) 624-2277

Proposed Plugging Method: PLUGGING PROPOSAL SAME AS PLUGGING REPORT.

Plugging Proposal Received By: KENNY SULLIVAN WitnessType: NONE
Date/Time Plugging Completed: 01/25/2013 2:00 PM KCC Agent: KENNY SULLIVAN

Actual Plugging Report:

SQUEEZE PERFS WITH 30 SX CMT & 200# HULLS. BACK OFF 2 7/8" LINER AT 4484'.
CUT 4 1/2" CASING & LOAD HOLE WITH MUD. 1ST PLUG AT 1530' WITH 50 SX
CMT. 2ND PLUG AT 550' WITH 40 SX CMT. 3RD PLUG AT 60' WITH 20 SX CMT.

Perfs:

Top	Bot	Thru	Comments
5805	5830	TBG	

Remarks: USED 60/40 POZMIX 4% GEL BY BASIC ENERGY.

Plugged through: TBG

District: 01

Signed

[Signature]
2/27/13
(TECHNICIAN)

RECEIVED

FEB - 6 2013

KCC DODGE CITY

RECEIVED
FEB 11 2013
KCC WICHITA

[Handwritten]