

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGIN
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-125-32220-00-00
Spot: NWSESWNE Sec/Twnshp/Rge: 9-35S-15E
3060 feet from S Section Line, 1665 feet from E Section Line
Lease Name: LONGHORN PROSPECT Well #: 14
County: MONTGOMERY Total Vertical Depth: 1262 feet

Operator License No.: 32937

Op Name: WATT, LARRY

Address: 399200 W 450 RD
COPAN, OK 74022

String	Size	Depth (ft)	Pulled (ft)	Comment
SURF	8.625	22	5	

Well Type: DH

UIC Docket No:

Date/Time to Plug: 08/14/2012 12:00 AM

Plug Co. License No.: 31696

Plug Co. Name: CUNNINGHAM CRUDE, A GENERAL PARTNERSHIP

Proposal Rcvd. from:

Company:

Phone:

Proposed Plugging Method: 50' plug at TD, 50' plug at 500' and 250' to surface.

Plugging Proposal Received By: DUANE SIMS

WitnessType: NONE

Date/Time Plugging Completed: 08/15/2012 2:00 PM

KCC Agent: DUANE SIMS

Actual Plugging Report:

Perfs:

Ran 1" to 1215' gelled hole and spotted 16 sack plug. Pulled up to 500' and spotted 16 sack plug. Pulled up to 250' and circulated cement to surface. Pulled 1" and topped well off. Came back next day and topped well off with 10 more sacks. At total of 93 sacks of cement were used to plug this well.

RECEIVED

APR 09 2013

KCC Chanute Dist. #3

DS

RECEIVED
KANSAS CORPORATION COMMISSION

APR 11 2013

CONSERVATION DIVISION
WICHITA, KS

Remarks:

Plugged through: TBG

District: 03

Signed

Duane G. Sims
4/25/13 (TECHNICIAN)