

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-035-19352-00-00
Spot: NENWNW Sec/Twnshp/Rge: 28-30S-7E
4920 feet from S Section Line, 4458 feet from E Section Line
Lease Name: SMITH Well #: 2
County: COWLEY Total Vertical Depth: 2854 feet

Operator License No.: 9576
Op Name: WHITEMAN, RON DBA GEN-DOR OIL C
Address: 8135 281ST RD
CAMBRIDGE, KS 67023

String	Size	Depth (ft)	Pulled (ft)	Comments
PROD	5.5	2827	779	
SURF		0		

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: 01/10/2013 8:00 AM
Plug Co. License No.: 9576 Plug Co. Name: WHITEMAN, RON DBA GEN-DOR OIL CO.
Proposal Rcvd. from: RON WHITEMAN Company: RON WHITEMAN/GENDOR OIL CO Phone: (620) 467-2615

Proposed Plugging Method: AS PER KC RULES & REGS

Plugging Proposal Received By: DUANE KRUEGER Witness Type: COMPLETE (100%)
Date/Time Plugging Completed: 01/11/2013 5:00 PM KCC Agent: DUANE KRUEGER

Actual Plugging Report:

Perfs:

MIRU RON WHITEMAN. RIH W/TBG @ 779' TAGGED SOLID. BRIDGE @ 779'.
CIRCULATED HOLE CLEAN. 1-11-2013, RIH W/TBG @ 770', MCPHERSON DRILLING
ESTABLISHED CIRCULATION MIXED & PUMPED 50 SXS CLASS A COMMON &
DISPLACED IN CASING. SHUT DOWN 10 MINUTES, CASINGS STANDING FULL @
SURFACE. LAYED TBG DOWN @ 360', MCPHERSON DRILLING ESTABLISHED
CIRCULATION MIXED & PUMPED 130 SXS CLASS A COMMON TO SURFACE.
CEMENT CIRCULATED. PLUG DOWN 1-11-2013 5:00 PM. MCPHERSON CEMENT
TICKET #27557, & 27560.

RECEIVED
KANSAS CORPORATION COMMISSION
APR 17 2013
CONSERVATION DIVISION
WICHITA, KS

Remarks: COMPLIANCE / RAW BORE HOLE/ CASING WAS PULLED FROM WELL @ PREVIOUS DATE.

Plugged through: TBG

District: 02

Signed

Duane Krueger
11/16/13 (TECHNICIAN)

✓