

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-009-24469-00-00
Spot: SWNWNW Sec/Twnshp/Rge: 2-16S-12W
4503 feet from S Section Line, 4863 feet from E Section Line
Lease Name: SIEFERS B Well #: B-5
County: BARTON Total Vertical Depth: 3358 feet

Operator License No.: 33480
Op Name: BORELL, ELVERN D.
Address: 178 N TURKEY RED RD
DIGHTON, KS 67839

String	Size	Depth (ft)	Pulled (ft)	Comments
PROD	4.5	3351		150 SX
SURF	8.625	531		240 SX

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: 03/22/2013 8:00 AM
Plug Co. License No.: 31529 Plug Co. Name: MIKE'S TESTING & SALVAGE, INC.
Proposal Rcvd. from: BILL SIEFERS Company: ELVERN BORELL Phone: (785) 658-7520

Proposed Plugging Method: Ordered 350 sx 60/40 pozmix 4% gel cement w/500 # hulls.
Perforations: 250', 750' and 1275'.

Plugging Proposal Received By: RAY DINKEL Witness Type: COMPLETE (100%)
Date/Time Plugging Completed: 03/22/2013 10:30 AM KCC Agent: RAY DINKEL

Actual Plugging Report:

Perfs:

Ran tubing to 3000' and pumped 100 sx cement w/100 # hulls.
Pulled tubing to 1500' and pumped 160 sx cement w/100 # hulls.
Cement circulated out braden head. Shut valve and pumped 70 sx cement to circulate out of casing.
POOH. Hooked to casing and pumped 20 sx cement at 300 psi.
GPS:38.69350 -098.62534

Remarks: COPELAND ACID AND CEMENTING TICKET # 383483

Plugged through: TBG

District: 04

Signed Ray A Dinkel
4/16/13 (TECHNICIAN)

CM

MAR 26 2013

Form CP-2/3

RECEIVED
KANSAS CORPORATION COMMISSION

APR 05 2013

CONSERVATION DIVISION
WICHITA, KS