

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-051-06330-00-01
Spot: SWSWNE Sec/Twnshp/Rge: 28-11S-17W
2970 feet from S Section Line, 2310 feet from E Section Line
Lease Name: FA BEMIS A Well #: #9
County: ELLIS Total Vertical Depth: 3410 feet

Operator License No.: 33263
Op Name: BOWMAN, WILLIAM F. DBA THE BILL
Address: 2640 W RD
NATOMA, KS 67651

String	Size	Depth (ft)	Pulled (ft)	Comments
PROD	7	3400		
SURF	10	1125		

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: 04/03/2013 9:00 AM
Plug Co. License No.: 6931 Plug Co. Name: BOWMAN OIL COMPANY, A GENERAL PARTNERSHIP
Proposal Rcvd. from: BILL BOWMAN Company: BOWMAN OIL COMPANY, A GENE Phone: (785) 434-2286

Proposed Plugging Method: Ordered 400 sx 60/40 pozmix 4% gel cement w/700 # hulls.
Emergency plug with rig over hole.
Drilled to 1683' and hole caved in.
ARB- 3400' - 3410
Top of 7" at 1574'.
GPS: 39.06798 -099.21220
2990' FSL 2264' FEL NE SW SW NE

Plugging Proposal Received By: CASE MORRIS WitnessType: COMPLETE (100%)
Date/Time Plugging Completed: 04/03/2013 11:30 PM KCC Agent: PAT STAAB

Actual Plugging Report:

Bowman ran in hole with tubing to 1650'. Swift pumped 125 sx cement w/300 # hulls mixed in.
Pulled tubing to 1175' and pumped 75 sx cement w/200 # hulls.
Pulled tubing to 600' and pumped 125 sx cement w/100 # hulls.
Pulled tubing to 150' and pumped 70 sx cement w/100 # hulls to circulate cement to surface.
Pulled tubing. Topped off 10" casing with 0 sx cement. Hole standing full.

Perfs:

Remarks: SWIFT SERVICES TICKET # 24037

Plugged through: TBG


RECEIVED
KANSAS CORPORATION COMMISSION

APR 08 2013

CONSERVATION DIVISION
WICHITA, KS

District: 04

Signed


4/16/13

(TECHNICIAN)

CM

APR 04 2013