

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-195-30160-00-00
Spot: NENESW Sec/Twnshp/Rge: 31-12S-21W
2308 feet from S Section Line, 2928 feet from E Section Line
Lease Name: MONROE Well #: 1
County: TREGO Total Vertical Depth: 4393 feet

Operator License No.: 6569
Op Name: CARMEN SCHMITT, INC.
Address: PO BOX 47
GREAT BEND, KS 67530

String	Size	Depth (ft)	Pulled (ft)	Comments
PROD	5.5	4100		125 SX
SURF	8.625	200		125 SX

Well Type: SWD UIC Docket No: D12179.0 Date/Time to Plug: 03/29/2013 3:00 PM
Plug Co. License No.: 6901 Plug Co. Name: D S & W WELL SERVICING, INC.
Proposal Rcvd. from: CURTIS HITSCHMANN Company: D S & W WELL SERVICING, INC. Phone: (620) 793-5100

Proposed Plugging Method: Ordered 450 sx 60/40 pozmix 4% gel cement w/600 # hulls and 12 sx gel.
Open hole well.
Shot perforations at 2400', 1730', 970' and 195'.

Plugging Proposal Received By: MARVIN MILLS WitnessType: COMPLETE (100%)
Date/Time Plugging Completed: 04/01/2013 3:00 PM KCC Agent: MARVIN MILLS

Actual Plugging Report:

Perfs:

Ran tubing to 3980' and pumped 12 sx gel followed by 75 sx cement w/250 # hulls.
Pulled tubing to 2428' and pumped 270 sx cement. Good circulation of cement.
Pulled tubing. Tied on to back side. Squeezed with 50 sx cement. Shut in pressure 150 psi.
Topped off casing w/50 sx cement. Still going down. Will check next week.
04/01/2013- Topped off casing with redi mix. Was 160' down. Is now full. Used 1 cubic yard of redi mix.

GPS: 38.96438 -099.69796

RECEIVED
KANSAS CORPORATION COMMISSION

Remarks: ALLIED CEMENTING TICKET # 59092

APR 05 2013

Plugged through: TBG

CONSERVATION DIVISION
WICHITA, KS

District: 04

Signed M Marvin Mills
4/16/13 (TECHNICIAN)

cc to UIC 4/08/13

CM

APR 02 2013