

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-015-22886-00-00
Spot: N2NWSWSW Sec/Twnshp/Rge: 20-24S-5E
1280 feet from S Section Line, 4950 feet from E Section Line
Lease Name: BLUESTEM B (BLACKSTONE) Well #: 9
County: BUTLER Total Vertical Depth: 2645 feet

Operator License No.: 33971
Op Name: TRIPower RESOURCES, LLC
Address: BOX 849
ARDMORE, OK 73402

String	Size	Depth (ft)	Pulled (ft)	Comments
PROD	4.5	2630		150 SX
SURF	8.625	217		150 SX
T1	2.375	2555		

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: 01/26/2013 12:00 AM
Plug Co. License No.: 5870 Plug Co. Name: PHILLIPS WELL SERVICE, INC.
Proposal Rcvd. from: GARY REED Company: _____ Phone: (316) 655-8775

Proposed Plugging Method: SPOT 50 SX ON BOTTOM, TAG PLUG, PERF @ 267', RUN TUBING TO 267' AND CIRCULATE TO SURFACE.

Plugging Proposal Received By: _____ WitnessType: PARTIAL
Date/Time Plugging Completed: 01/28/2013 12:00 AM KCC Agent: PATRICK SHIELDS

Actual Plugging Report:

1/26 TRIPPED TUBING TO 2558' AND PUMPED 35 SX OF 60 X 40, 2 % GEL, 3% CAL, 1/4 LB FLOW SEAL. TAGGED @ 2042', PERFED @ 279' AND CIRCULATED 112 SX TO SURFACE. 1/28 TOPPED OFF W/ 35 SX.

Perfs:

Top	Bot	Thru	Comments
2556	2566	TBG	


RECEIVED
FEB 08 2013
KCC WICHITA

Remarks:

Plugged through: TBG

District: 02

Signed


01/28/13

(TECHNICIAN)

✓ JK