

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-135-22657-00-00
Spot: NESENE Sec/Twnshp/Rge: 20-17S-24W
1635 feet from N Section Line, 295 feet from E Section Line
Lease Name: SIDEBOTTOM Well #: 5
County: NESS Total Vertical Depth: 4389 feet

Operator License No.: 31788
Op Name: VEENKER RESOURCES, INC.
Address: PO BOX 14339
OKLAHOMA CITY, OK 73113

String	Size	Depth (ft)	Pulled (ft)	Comment
MSCC	5.5	1040		WITH 450 SX CMT
PROD	5.5	4380	0	WITH 200 SX CMT
SURF	8.625	290		

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: 01/23/2013 8:00 AM
Plug Co. License No.: 6454 Plug Co. Name: CHEYENNE WELL SERVICE, INC.
Proposal Rcvd. from: MARK VEENKER Company: VEENKER RESOURCES Phone: (405) 751-1414

Proposed Plugging Method: RUN TBG TO 4310' & PUMP 10 SX GEL & 40 SX CMT. PULL TBG TO 1040'. CIRCULATE CMT TO SURFACE UP 5 1/2". PULL TBG OUT & TOP OFF HOLE. PRESSURE TEST 8 5/8" X 5 1/2" ANNULUS TO 500 PSIG WITH CMT.

Plugging Proposal Received By: RICHARD LACEY Witness Type: COMPLETE (100%)
Date/Time Plugging Completed: 01/23/2013 11:50 AM KCC Agent: RICHARD LACEY

Actual Plugging Report:

RAN TBG TO 4300'. PUMPED 10 SX GEL - 150# HULLS - 40 SX CMT. PULLED TBG TO 1240'. PUMPED 160 SX CMT CIRCULATING CMT TO SURFACE. PULLED TBG OUT OF HOLE & TOPPED OFF 5 1/2" WITH 15 SX CMT. VISUALLY CHECKED 8 5/8" X 5 1/2" ANNULUS & IT WAS FULL OF CMT.

Perfs:

Remarks: **COMPLIANCE ISSUE: DENIED TA 10 YR RULE** USED 60/40 POZMIX 4% GEL BY SWIFT SERVICES.

Plugged through: TBG

District: 01

RECEIVED

JAN 30 2013

KCC DODGE CITY

Signed

Richard W. Lacey
3/04/13

(TECHNICIAN)

RECEIVED
FEB 25 2013
KCC WICHITA

RWL