

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-015-23474-00-00
Spot: SWNWNWNW Sec/Twnshp/Rge: 28-25S-5E
4813 feet from S Section Line, 5063 feet from E Section Line
Lease Name: HEGBERG A Well #: 201
County: BUTLER Total Vertical Depth: 760 feet

Operator License No.: 5030
Op Name: VESS OIL CORPORATION
Address: 1700 WATERFRONT PKWY BLDG 500
WICHITA, KS 67206

String	Size	Depth (ft)	Pulled (ft)	Comments
PROD	5.5	759		125 SX
SURF	8.625	217		110 SX

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: 01/09/2013 8:00 AM
Plug Co. License No.: 32991 Plug Co. Name: SIMMONS WELL SERVICE, INC.
Proposal Rcvd. from: CASEY COATS Company: VESS OIL CORP Phone: (316) 655-1997

Proposed Plugging Method: AS PER KCC RULES & REGS

Plugging Proposal Received By: DUANE KRUEGER Witness Type: COMPLETE (100%)
Date/Time Plugging Completed: 01/09/2013 9:00 AM KCC Agent: DUANE KRUEGER

Actual Plugging Report:

RIH W/TBG /2 670', CONSOLIDATED OILWELL SERVICES MIXED & PUMPED 80 SXS 60/40 POZMIX 4% GEL, 2% CC TO SURFACE. CEMENT CIRCULATED. LAYED DOWN TBG, SWEDGED INTO 5-1/2" CASING AND PUMPED 5 MORE SXS. SHUT IN UNDER PRESSURE (500 #). PLUG DOWN 9:00 AM, 1-9-2013, CONSOLIDATED CEMENT TICKET #35454.

Perfs:


Top	Bot	Thru	Comments
674	691	CSG	
562	570	CSG	

Remarks: DENIED TA/ LENGTH OF TIME

Plugged through: TBG

District: 02

Signed


8/09/13 (TECHNICIAN)

RECEIVED
JAN 17 2013

KCC WICHITA

✓