

TO:  
STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING  
130 SOUTH MARKET, SUITE 2078  
WICHITA, KANSAS 67202

API Well Number: 15-095-30249-00-00  
Spot: NESW Sec/Twnshp/Rge: 36-30S-7W  
3300 feet from N Section Line, 3300 feet from E Section Line  
Lease Name: RUSSELL Well #: 2  
County: KINGMAN Total Vertical Depth: 4708 feet

Operator License No.: 5030  
Op Name: VESS OIL CORPORATION  
Address: 1700 WATERFRONT PKWY BLDG 500  
WICHITA, KS 67206

String	Size	Depth (ft)	Pulled (ft)	Comments
CIBP		4410		
PROD	5.5	4705	2550	100 SX
SURF	8.625	227		165 SX

Well Type: GAS UIC Docket No: \_\_\_\_\_ Date/Time to Plug: 02/07/2013 12:00 AM

Plug Co. License No.: 31529 Plug Co. Name: MIKE'S TESTING & SALVAGE, INC.

Proposal Rcvd. from: MIKE KELSO Company: MIKE'S TESTING & SALVAGE, INC. Phone: \_\_\_\_\_

Proposed Plugging Method: Per KCC District 2 instructions

Plugging Proposal Received By: STEVE VANGIESON

Witness Type: PARTIAL

Date/Time Plugging Completed: 02/07/2013 5:00 PM

KCC Agent: B. J. HOPE

Actual Plugging Report:

SANDED BACK TO 4250' - CAPPED WITH 5 SX CEMENT ON TOP. CUT CASING PIPE OFF @ 2550' PULLED CASING TO 1281' SPOTTED 35 SX CEMENT. WAITED 1.5 HOURS TAGGED PLUG @ 1053'. PULLED CASING TO 850' SPOTTED 35 SX CEMENT. PULLED CASING TO 285' CIRCULATED TO SURFACE WITH 150 SX CEMENT.

Perfs:

Top	Bot	Thru	Comments
4707	4708		
4329	4335		

Remarks: COPELAND CEMENTING OUT OF GREAT BEND, 60/40 4% POS MIX

Plugged through: CSG

District: 02

Signed B. J. Hope  
2/7/13 (TECHNICIAN)

RECEIVED

FEB 20 2013

KCC WICHITA

Form CP-2/3