

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-095-21715-00-00
Spot: S2N2SESW Sec/Twnshp/Rge: 36-30S-7W
710 feet from S Section Line, 1980 feet from W Section Line
Lease Name: RUSSELL A Well #: 3
County: KINGMAN Total Vertical Depth: 4500 feet

Operator License No.: 5030
Op Name: VESS OIL CORPORATION
Address: 1700 WATERFRONT PKWY BLDG 500
WICHITA, KS 67206

String	Size	Depth (ft)	Pulled (ft)	Comments
PROD	5.5	4496	2600	100 SX
SURF	8.625	225		150 SX

Well Type: GAS UIC Docket No: _____ Date/Time to Plug: 02/06/2013 12:00 AM
Plug Co. License No.: 31529 Plug Co. Name: MIKE'S TESTING & SALVAGE, INC.
Proposal Rcvd. from: JAMIE Company: MIKE'S TESTING & SALVAGE, INC. Phone: _____

Proposed Plugging Method: SAND TO 4286' - 5 SKS CEMENT, 1350' 35 SXS, 850' 35 SX'S, CIRC 300'-0'.

Plugging Proposal Received By: HUNTER CLARK Witness Type: COMPLETE (100%)
Date/Time Plugging Completed: 02/06/2013 4:00 PM KCC Agent: STEVE VANGIESON

Actual Plugging Report:

THE PERFS WERE COVERED WITH SAND 4250' & CAPPED WITH 5 SKS CEMENT. CASING RECOVERED FROM 2600' & PULLED TO 1350' WHERE 35 SX OF CEMENT WAS SPOTTED. WAITED 1 HOUR & TAGGED. PLUG IN PLACE. SPOTTED 35 SK PLUG AT 850'. PULLED CASING TO 300' & CIRC'D CEMENT TO SURFACE.

Perfs:

Top	Bot	Thru	Comments
4336	4350	CSG	

Remarks: COPELAND ACID

Plugged through: CSG

District: 02

Signed _____

[Handwritten Signature]
3/04/13 (TECHNICIAN)

RECEIVED CP-2/3
FEB 20 2013
KCC WICHITA