

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-081-22008-00-00
Spot: NWSENEW Sec/Twnshp/Rge: 24-29S-33W
1860 feet from S Section Line, 2120 feet from W Section Line
Lease Name: BIRNEY TRUST B Well #: 2
County: HASKELL Total Vertical Depth: 5829 feet

Operator License No.: 5447
Op Name: OXY USA INC.
Address: 5 E GREENWAY PLZ PO BOX 27570
HOUSTON, TX 77227

String	Size	Depth (ft)	Pulled (ft)	Comment
SURF	8.625	1841		WITH 595 SX CMT

Well Type: DH UIC Docket No: _____ Date/Time to Plug: 01/30/2013 6:00 PM
Plug Co. License No.: 34660 Plug Co. Name: AZTEC WELL SERVICING CO.
Proposal Rcvd. from: EARLY ZION Company: AZTEC WELL SERVICING CO. Phone: (505) 334-6194

Proposed Plugging Method: 1ST PLUG AT 1950' WITH 100 SX CMT. 2ND PLUG AT 750' WITH 50 SX CMT. 3RD PLUG AT 60' WITH 20 SX CMT. NO RAT HOLE. 4TH PLUG TO CIRCULATE MOUSE HOLE WITH 20 SX CMT.

Plugging Proposal Received By: KENNY SULLIVAN WitnessType: NONE
Date/Time Plugging Completed: 01/30/2013 8:00 PM KCC Agent: KENNY SULLIVAN

Actual Plugging Report:

Perfs:

1ST PLUG AT 1948' WITH 100 SX CMT. 2ND PLUG AT 750' WITH 50 SX CMT. 3RD PLUG AT 60' WITH 20 SX CMT. NO RAT HOLE. 4TH PLUG TO CIRCULATE MOUSE HOLE WITH 20 SX CMT.

Remarks: USED 60/40 POZMIX 4% GEL BY ALLIED.

Plugged through: DP

RECEIVED
FEB 11 2013
KCC WICHITA

District: 01

Signed [Signature]
(TECHNICIAN)

RECEIVED
FEB - 6 2013
KCC DODGE CITY

[Handwritten mark]