

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-109-21146-00-00
Spot: NWNESWSE Sec/Twnshp/Rge: 17-15S-33W
1230 feet from S Section Line, 1748 feet from E Section Line
Lease Name: LPR Well #: 1-17
County: LOGAN Total Vertical Depth: 4685 feet

Operator License No.: 6044
Op Name: STELBAR OIL CORPORATION, INC.
Address: 1625 N WATERFRONT PKWY
WICHITA, KS 67206

String	Size	Depth (ft)	Pulled (ft)	Comments
PROD	4.5	4615		525 sx
SURF	8.625	303		225 sx

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: 02/14/2013 2:00 PM
Plug Co. License No.: 33645 Plug Co. Name: H2 PLAINS, LLC
Proposal Rcvd. from: _____ Company: H2 PLAINS, LLC Phone: (785) 798-3995

Proposed Plugging Method: Ordered 300 sx 60/40 pozmix 4% gel cement.
Perforations at 4275' to 4300'.
DV tool at 2357' with 400 sx cement. Fell Back to 770'. Ran 1" pipe down to 770' and pumped 125 sx cement to surface.

Plugging Proposal Received By: CASE MORRIS WitnessType: COMPLETE (100%)
Date/Time Plugging Completed: 02/14/2013 6:00 PM KCC Agent: MARVIN MILLS

Actual Plugging Report:

Perfs:

Ran tubing to 4100' and pumped 9 sx gel followed with 50 sx cement.
Pulled tubing to 2350' and pumped 125 sx cement.
Pulled tubing to 1100' and pumped 85 sx cement. Good circulation of cement.
Pulled tubing out. Topped off with 50 sx cement full.
Back side is full.

Remarks: BASIC CEMENT TICKET # 171703257

Plugged through: TBG

RECEIVED
MAR 04 2013
KCC WICHITA

District: 04

Signed


(TECHNICIAN)

CM

FEB 18 2013