

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-163-20015-00-02
Spot: SWNWSESW Sec/Twnshp/Rge: 6-8S-20W
891 feet from S Section Line, 3653 feet from E Section Line
Lease Name: THYFAULT Well #: 3
County: ROOKS Total Vertical Depth: 3667 feet

Operator License No.: 3134
Op Name: MORRIS, TERRY E. DBA G L M COMPA
Address: PO BOX 193
RUSSELL, KS 67665

String	Size	Depth (ft)	Pulled (ft)	Comments
L1	4.5	1221		Top 700'
PROD	4.5	1221		250 SX
PROD	5.5	3600		
SURF	10.75	257		
SURF	7	3600		275 SX
T1	2.375	1149		

Well Type: SWD UIC Docket No: D13730.0 Date/Time to Plug: 04/24/2013 10:00 AM
Plug Co. License No.: 32810 Plug Co. Name: PROFESSIONAL PULLING SERVICES LLC
Proposal Rcvd. from: JEFF PFANNENSTIEL Company: PROFESSIONAL PULLING SERVIC Phone: (785) 628-7443

Proposed Plugging Method: Ordered 200 sx 60/40 pozmix 4% gel cement w/600 # hulls.
Cedar Hills: 1147' - 1187'
7" casing to top. 4 1/2" liner at 700' to 1221' cemented w/250 sx cement.

Plugging Proposal Received By: RICHARD WILLIAMS WitnessType: COMPLETE (100%)
Date/Time Plugging Completed: 04/24/2013 1:30 PM KCC Agent: RICHARD WILLIAMS

Actual Plugging Report:

Ran 2 3/8" tubing to 1100'. Quality Oilwell Cementing pumped 150 sx 60/40 pozmix 4% gel w/500 # hulls. Circulated cement.
PTOH. Topped casing off w/25 sx cement.
Backside full of cement.

GPS: 39.38214 -99.59761

Perfs:

Top	Bot	Thru	Comments
1147	1187		

Remarks: QUALITY OILWELL CEMENTING

Plugged through: TBG

RECEIVED
KANSAS CORPORATION COMMISSION

MAY 06 2013

CONSERVATION DIVISION
WICHITA, KS

District: 04

Signed Richard Williams
(TECHNICIAN)

CM

APR 26 2013