

TO: STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING  
130 SOUTH MARKET, SUITE 2078  
WICHITA, KANSAS 67202

API Well Number: 15-175-21990-00-00  
Spot: S2NWNW Sec/Twnshp/Rge: 20-34S-33W  
990 feet from N Section Line, 660 feet from W Section Line  
Lease Name: STEVESON A Well #: 5  
County: SEWARD Total Vertical Depth: 6650 feet

Operator License No.: 5447  
Op Name: OXY USA INC.  
Address: 5 E GREENWAY PLZ PO BOX 27570  
HOUSTON, TX 77227

String	Size	Depth (ft)	Pulled (ft)	Comment
CIBP		1700		WITH 4 SX CMT
PC		3106		
PROD	4.5	6640	1218	WITH 615 SX CMT
SURF	8.625	1688		WITH 815 SX CMT

Well Type: GAS UIC Docket No: \_\_\_\_\_ Date/Time to Plug: 04/19/2013 9:00 AM  
Plug Co. License No.: 32833 Plug Co. Name: SARGENT LILLARD CASING PULLING, INC.  
Proposal Rcvd. from: KIRBY LILLARD Company: SARGENT LILLARD CASING PULL Phone: (580) 254-1881

Proposed Plugging Method: PUMP 250# HULLS & 20 SX CMT ON BOTTOM. PLUG AT 1720' WITH 50 SX CMT. PLUG AT 550' WITH 50 SX CMT. PLUG AT 40' WITH 10 SX CMT.

Plugging Proposal Received By: KEN JEHLIK WitnessType: NONE  
Date/Time Plugging Completed: 04/19/2013 5:00 PM KCC Agent: KEN JEHLIK

Actual Plugging Report:

PUMP 30 SX CMT & 250# HULLS ON BOTTOM. 1ST PLUG SET CIBP @ 1700' WITH 4 SX CMT. 2ND PLUG AT 550' WITH 50 SX CMT. 3RD PLUG AT 40' WITH 10 SX CMT.

Perfs:

Top	Bot	Thru	Comments
6156	6190		

Remarks: USED COMMON CEMENT BY SARGENT LILLARD.

Plugged through: CSG

RECEIVED  
KANSAS CORPORATION COMMISSION

APR 29 2013

CONSERVATION DIVISION  
WICHITA, KS

District: 01

RECEIVED  
APR 23 2013  
KCC DODGE CITY

Signed

*[Handwritten Signature]*  
5/16/13

(TECHNICIAN)

*[Handwritten Mark]*