

TO:  
STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING  
130 SOUTH MARKET, SUITE 2078  
WICHITA, KANSAS 67202

API Well Number: 15-055-21000-00-00  
Spot: SWSWNW Sec/Twnshp/Rge: 8-23S-30W  
2970 feet from S Section Line, 4950 feet from E Section Line  
Lease Name: HAAG Well #: 4-8  
County: FINNEY Total Vertical Depth: 4886 feet

Operator License No.: 32198  
Op Name: PETROSANTANDER (USA) INC.  
Address: 6363 WOODWAY DR STE350  
HOUSTON, TX 77057

String	Size	Depth (ft)	Pulled (ft)	Comment
CIBP		2040		
CIBP		4690		WITH 2 SX CMT
DVT		2050		WITH 450 SX CMT
PROD 4.5		4885	0	WITH 150 SX CMT
SURF 8.625		371		WITH 210 SX CMT

Well Type: OIL UIC Docket No: \_\_\_\_\_ Date/Time to Plug: 04/23/2013 9:00 AM  
Plug Co. License No.: 33961 Plug Co. Name: CONSOLIDATED OIL WELL SERVICES LLC  
Proposal Rcvd. from: CARLOS Company: PETROSANTANDER Phone: (713) 784-8700

Proposed Plugging Method: SET CIBP @ 2050'. FILL WITH CMT FROM 2050'-0'.

Plugging Proposal Received By: RICHARD LACEY Witness Type: PARTIAL  
Date/Time Plugging Completed: 04/23/2013 1:00 PM KCC Agent: KEN JEHLIK

Actual Plugging Report:

\*\*CASING LEAKS 2164'-3037'.\*\* CIBP @ 4690' WITH 2 SX CMT. CIBP @ 2040'. RUN TBG TO 1975' & FILL 4 1/2" CASING TO 0' IN TWO STAGES USING A TOTAL OF 160 SX CMT. TOOH W/TBG & TOP OFF WITH 10 SX CMT. PUMP 15 SX CMT DOWN THE ANNULUS TO 300#. HOLDING.

Perfs:

Top	Bot	Thru	Comments
4752	4757		MISSISSIPPI
3883	3912		TOPEKA

Remarks: USED 60/40 POZMIX 4% GEL BY CONSOLIDATED.

Plugged through: TBG

RECEIVED  
KANSAS CORPORATION COMMISSION

MAY 01 2013

CONSERVATION DIVISION  
WICHITA, KS

District: 01

RECEIVED

APR 26 2013

KCC DODGE CITY

Signed

(TECHNICIAN)