

TO:  
STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING  
130 SOUTH MARKET, SUITE 2078  
WICHITA, KANSAS 67202

API Well Number: 15-051-24795-00-00  
Spot: W2NENWSW Sec/Twnshp/Rge: 35-13S-20W  
2310 feet from S Section Line, 750 feet from W Section Line  
Lease Name: ARCO-DREILING Well #: 1-35  
County: ELLIS Total Vertical Depth: 3920 feet

Operator License No.: 30606  
Op Name: MURFIN DRILLING CO., INC.  
Address: 250 N WATER STE 300  
WICHITA, KS 67202

String	Size	Depth (ft)	Pulled (ft)	Comments
CIBP		3600		
CIBP		3800		
PROD	5.5	3919		490 SX
SURF	8.625	273		170 SX

Well Type: OIL UIC Docket No: \_\_\_\_\_ Date/Time to Plug: 04/04/2013 1:00 PM  
Plug Co. License No.: 30606 Plug Co. Name: MURFIN DRILLING CO., INC.  
Proposal Rcvd. from: CRAIG Company: MURFIN DRILLING CO., INC. Phone: (785) 623-0123

Proposed Plugging Method: Tubing to 3100'. Pumped 7 sx gel followed by 50 sx cement w/250 # hulls.  
Tubing to 2000'. Pumped 100 sx cement w/150 # hulls.  
Tubing to 1000'. Pumped 75 sx cement w/100 # hulls.  
Pulled tubing. Squeezed 8 5/8" casing w/60 sx cement.  
Ordered 335 sx 60/40 pozmix 4% gel cement., 500 # hulls and 7 sx gel.

Plugging Proposal Received By: CASE MORRIS WitnessType: COMPLETE (100%)  
Date/Time Plugging Completed: 04/04/2013 1:00 PM KCC Agent: TOM CULLEY

Actual Plugging Report:

Ran tubing to 3100' and pumped 7 sx gel followed by 50 sx cement w/150 # hulls.  
Pulled tubing to 2000' and pumped 100 sx cement w/150 # hulls.  
Pulled tubing to 1000' and pumped 75 sx cement w/250 # hulls. Cement circulated.  
Pulled all tubing. Pumped 10 sx cement. Shut in pressure 300 psi.  
Squeezed 8 5/8" casing w/15 sx cement. Shut in pressure 300 psi.  
Packer stuck in hole at 3224'. Perforations at 3537' - 3539', 3644' - 3648', 3672' - 3676', 3694' - 3696' and 3822' - 3824'.  
GPS: 38.87696 -099.51892

Perfs:

Top	Bot	Thru	Comments
3822	3824		
3694	3696		
3672	3676		
3644	3648		
3537	3539		

RECEIVED  
KANSAS CORPORATION COMMISSION

Remarks: QUALITY OILWELL CEMENTING TICKET # 6729

APR 22 2013

Plugged through: TBG

CONSERVATION DIVISION  
WICHITA, KS

District: 04

Signed

Tom Culley  
4/26/13 (TECHNICIAN) CM

APR 10 2013