

TO: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-129-21669-00-00
Spot: E2NWNWNE Sec/Twnshp/Rge: 8-33S-42W
330 feet from N Section Line, 2110 feet from E Section Line
Lease Name: HENTSCHEL B Well #: 1
County: MORTON Total Vertical Depth: 5100 feet

Operator License No.: 5447
Op Name: OXY USA INC.
Address: 5 E GREENWAY PLZ PO BOX 27570
HOUSTON, TX 77227

| String | Size | Depth (ft) | Pulled (ft) | Comment |
|--------|-------|------------|-------------|-----------------|
| PC | | 3193 | | WITH 205 SX CMT |
| PROD | 5.5 | 5106 | 463 | WITH 410 SX CMT |
| SURF | 8.625 | 1436 | | WITH 615 SX CMT |

Well Type: GAS UIC Docket No: _____ Date/Time to Plug: 01/17/2013 1:00 PM
Plug Co. License No.: 32833 Plug Co. Name: SARGENT LILLARD CASING PULLING, INC.
Proposal Rcvd. from: JOHN SCHOOLCRAFT Company: SARGENT LILLARD CASING PULL Phone: (580) 254-1881

Proposed Plugging Method: LOAD HOLE WITH MUD. PLUG AT 1460' WITH 50 SX CMT. PLUG AT 430' WITH 40 SX CMT. PLUG AT 40' WITH 10 SX CMT.

Plugging Proposal Received By: STEVE PFEIFER WitnessType: NONE
Date/Time Plugging Completed: 01/22/2013 1:00 PM KCC Agent: STEVE PFEIFER

Actual Plugging Report:

****JUNK IN HOLE: 5 JTS TBG WITH ANCHOR CATCHER. TOP OF FISH @ 4280'.****
PUMP 50 SX COMMON CEMENT WITH 150# HULLS TO 4280'. TAG CMT TOP @ 3783'. SHOT OFF A COLLAR @ 1458' & TAKE INJECTION RATE @ 1200# DECREASING TO 600#. PUMP 50 SX CMT THROUGH BLOWN COLLAR @ 1458', LEAVING 15 SX CMT INSIDE 5 1/2" CASING. PUMP 40 SX CMT AT 440'. PUMP 10 SX CMT AT 40'.

Perfs:

| Top | Bot | Thru | Comments |
|------|------|------|----------|
| 4553 | 4582 | | |

Remarks: USED COMMON CEMENT BY SARGENT LILLARD.

Plugged through: CSG

RECEIVED
FEB 09 2013
KCC WICHITA

District: 01

Signed [Signature]
(TECHNICIAN)

RECEIVED
JAN 29 2013
KCC DODGE CITY

[Handwritten mark]