

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-129-20933-00-00
Spot: NENWSENE Sec/Twnshp/Rge: 8-34S-42W
3938 feet from S Section Line, 939 feet from E Section Line
Lease Name: INTERSTATE E Well #: 2
County: MORTON Total Vertical Depth: 4400 feet

Operator License No.: 5447
Op Name: OXY USA INC.
Address: 5 E GREENWAY PLZ PO BOX 27570
HOUSTON, TX 77227

String	Size	Depth (ft)	Pulled (ft)	Comment
COND	20	50		WITH 4 SX CMT
DVT		3099		
PROD	5.5	4399	0	WITH 925 SX CMT
SURF	8.625	1255		WITH 750 SX CMT

Well Type: GAS UIC Docket No: _____ Date/Time to Plug: 01/23/2013 9:00 AM
Plug Co. License No.: 32833 Plug Co. Name: SARGENT LILLARD CASING PULLING, INC.
Proposal Rcvd. from: JOHN SCHOOLCRAFT Company: SARGENT LILLARD CASING PULL Phone: (580) 254-1881

Proposed Plugging Method: 200# HULLS WITH 35 SX CMT. SPCAER TO 1355'. 25 SX CMT AT 1355'. SPACER TO 600'. 25 SX CMT AT 600'. SPACER TO 40'. 10 SX CMT AT 40' TO 0'.

Plugging Proposal Received By: KEN JEHLIK WitnessType: COMPLETE (100%)
Date/Time Plugging Completed: 01/23/2013 1:00 PM KCC Agent: KEN JEHLIK

Actual Plugging Report:

PUMP 35 SX CMT & 200# HULLS TO 4252'. MUD SPACER TO 1355'. TAG WITH SLICK LINE FLOAT. PUMP 25 SX CMT AT 1355'. SPACER TO 600'. PUMP 25 SX CMT AT 600'. SPACER TO 40'. PUMP 6 SX CMT FROM 40' TO 0'. PRESSURE TO 300#. HOLDING. PUMP 4 SX CMT DOWN ANNULUS TO 150#.

Perfs:

Top	Bot	Thru	Comments
4242	4252		

Remarks: USED COMMON CEMENT BY SARGENT LILLARD.

Plugged through: CSG


District: 01

RECEIVED

JAN 29 2013

KCC DODGE CITY

Signed



(TECHNICIAN)

RECEIVED
FEB 09 2013
KCC WICHITA